

ADDENDUM NUMBER ONE

**HCPS ENTRANCE SECURITY RENOVATIONS
HENDERSON COUNTY PUBLIC SCHOOLS**

MLA PROJECT NUMBER: 18006

Mark Lusk Architecture, PLLC
128 Woodburn Drive
Swannanoa, NC 28778
(828) 808-9757

DATE OF ISSUE: November 26, 2018

TO: ALL BIDDERS OF RECORD

This Addendum modifies the Contract Documents only in the manner and to the extent stated herein and shown on any accompanying drawings and will become a part of the Contract Documents. Except as specified or otherwise indicated by this Addendum, all work shall be in accordance with the basic requirements of the Contract Documents.

BIDDERS SHALL ACKNOWLEDGE RECEIPT OF ADDENDUM ON BID FORM.

This Addendum consists of one page(s) and any enclosures noted:

I. ENCLOSURES:

1. None

II. GENERAL INFORMATION / CLARIFICATIONS:

1. None

III. CHANGES TO PROJECT MANUAL:

1. None

IV. CHANGES TO DRAWINGS:

Sheet A201:

1. Plan 2 WHHS:
 - a. Door #3-Remove existing stud wall at hinge side and locate door frame against corner
 - b. Door #4-Reverse existing door and provide continuous hinge
 - c. Conference Room Door shall be Door #7. ADD the following to Hardware Notes-"7. Conference Room Door: Provide mortise lockset (Classroom function) closer, hinges".
 - d. Conference Room walls shall extend above ceiling. Rework existing ceiling grid and ceiling tile to terminate at walls.
2. Plan 3 EES:
 - a. ADD the following to Door #3 note: "with HM frame 45 min rated. Remove existing window and provide framed opening"
 - b. Revise Construction Notes- Door #3: -".Lobby Door: Provide mortise lockset (Classroom function) closer, hinges".
 - c. HM frame/glass wall shall be located 12" clear of existing door #4.
 - d. SRO Office Door shall be Door #6. ADD the following to Construction Notes-"6. SRO Office Door: Provide mortise lockset (Classroom function) closer, hinges". Provide 45min HM frame.

END OF ADDENDUM