



## Henderson County Capital Projects

100 North King Street, Suite 206  
Hendersonville, North Carolina 28792

---

*Memorandum To: Interested Qualified Bidders*

*From: Thad Ninnemann  
Henderson County Capital Projects Project Manager*

*Subject: Addendum #1  
New Hendersonville High School: Supply and Install  
Kitchen Equipment*

*Date: June 10, 2020*

---

### **Addendum #1 Clarifications**

Please see below for the following clarifications on specific kitchen equipment items to be provided as identified on drawing AK-101 for the New Hendersonville High School. Acknowledgement of this addendum is required for the acceptance of proposals for this project.

- K4** Provide Champion 44PRO dishwasher supplied with relay for condensate fan and stainless-steel pant leg duct extending 12" above ceiling.
- K5** Dishwasher to be supplied with built in booster
- K8** Delete this component, Specification Section 114000 Part 4 Item K8 Sink Heater not required
- K11** Manufactured by Low Temp
- K12** Manufactured by Low Temp
- K13** Manufactured by Low Temp
- K14** Manufactured by Low Temp
- K17** Manufactured by Low Temp
- K18** Manufactured by Low Temp



## **Henderson County Capital Projects**

100 North King Street, Suite 206

Hendersonville, North Carolina 28792

- K19**    Manufactured by Low Temp
- K50**    Manufactured by Low Temp
- K20**    True Stainless-Steel Model STR2-HPT-2S-2S
- K21**    True Stainless-Steel Model STR1-RPT-2S-2S
- K26**    Southbend GTS-40 Skillet with T&S HG-4D-48SK gas hose
- K27**    Supply Convection oven with T&S HG-4D-48SK gas hose
- K28**    Provide with 1900.1150WS Water filters and T&S HG-4D-48SK gas hoses
- K29**    Pitco Fryer supplied with T&S HG-4D-48SK gas hose
- K51**    Brown Walk-In-Cooler supplied with 66" x 18" access panel above cooler door
- K52**    Brown Walk-In-Freezer with Hand Truck Floor and heat tape for condensate drain line
- K60**    True Stainless-Steel Model STR2R-2S-HC Refrigerator
- K61**    True Stainless-Steel Model STR2F-2S-HC Freezer

Again, I want to re-iterate that there will be required coordination with the HVAC, Plumbing, and Electrical contractors with the kitchen equipment installation especially, but not limited to, as it relates to the UDS and hood installations.