

ADDENDUM NUMBER TWO

**RMS & FRMS GYMS, WHHS BLDG Y & HCPS C.O. ROOF REPLACEMENTS
HENDERSON COUNTY PUBLIC SCHOOLS**

MLA PROJECT NUMBER: 20004

Mark Lusk Architecture, PLLC
128 Woodburn Drive
Swannanoa, NC 28778
(828) 808-9757

DATE OF ISSUE: July 2, 2020

TO: ALL BIDDERS OF RECORD

This Addendum modifies the Contract Documents only in the manner and to the extent stated herein and shown on any accompanying drawings and will become a part of the Contract Documents. Except as specified or otherwise indicated by this Addendum, all work shall be in accordance with the basic requirements of the Contract Documents.

BIDDERS SHALL ACKNOWLEDGE RECEIPT OF ADDENDUM ON BID FORM.

This Addendum consists of two page(s) and any enclosures noted. Any enclosure shall replace an existing previously published document or add to the bid documents as a new document:

I. ENCLOSURES:

1. None

II. GENERAL INFORMATION / CLARIFICATIONS:

1. None

III. CHANGES TO PROJECT MANUAL:

1. None

IV. CHANGES TO DRAWINGS:

1. A204:
 - a. Downspout replacements shall match existing in size- 3"x4".
 - b. Revise Roofing Notes as follows:
 - Note 1. "Concrete Plank Roof Deck" is revised to "Gypsum Plank Roof Deck"
 - Note 2. "Including lightweight concrete" is removed from the note. The existing lightweight concrete shall remain.
 - Note 3. "Fully adhere tapered insulation to concrete roof deck" is revised to "Mechanically attach tapered insulation through lightweight concrete into gypsum plank roof deck"
2. A205: The 3 overflow roof drains shall remain as is and a sump created around each roof drain in the tapered insulation per detail 3/A301. Their use will be converted from overflow roof drains to roof drains.

END OF ADDENDUM