

### Addendum #3 Killian Building Chiller Replacement

Additional specifications for Option B: Provide and Replace chiller circulating pump and controls needed to meet specifications in revised engineered drawing.

The VFD speed for the new pump will need to be controlled by the Metasys and integrated with Metasys. This will be part of the Contractor's scope of work. The Contractor will need to include this in his pricing for Option B. The drive is 7.5hp. Below is a link to the drive's project information:

<https://www.yaskawa.com/products/drives/hvac-drives/fan-pump-drives/hv600-drive>