



## Henderson County Capital Projects

100 North King Street, Suite 206

Hendersonville, North Carolina 28792

### **Addendum #1**

*Upward Elementary School – Paving Improvements*

**April 3, 2023**

This Addendum shall be attached to and made a part of the above named Contract Documents.

The following items are issued to, modify, and clarify the Contract Documents. These items shall have full force and effect as the Contract Documents, and cost involved shall be included in the Bid prices. Bids, to be submitted on the specified date, shall conform to the additions and revisions listed herein.

Acknowledge receipt of the Addendum on the Bid. Failure to do so may subject the bidder to disqualification.

#### ADDENDUM ITEMS

- I. The bid-form has been updated to add a line item for:
  - a. Mobilization, Insurance, and Construction Staking
  - b. Misc. Sitework for Reconfigured Island
2. All responsible bidders shall use the revised bid-form dated 4/3/2023.

END OF ADDENDUM #1

**HENDERSON COUNTY PUBLIC SCHOOLS**  
**2022 Paving, Pavement Repairs, Resurfacing, & Striping**  
 Bid Schedule 4.3.2023

Bidder \_\_\_\_\_

Plans: Henderson County Public Schools 2022 Paving

**Bids Due: April 6th, 2023 @ 2:00 PM**

Receipt of the following **addenda** is hereby acknowledged:

Addendum No.	Addendum Date	
_____ 1 _____	_____ 4.3.2023 _____	
_____	_____	
_____	_____	

No.	DESCRIPTION	UNIT QTY	UNIT PRICE	TOTAL PRICE
-----	-------------	----------	------------	-------------

Upward Elementary School				
1	Mobilization, Insurance, and Construction Staking	LS	1	
<b>SUBTOTAL</b>				

Upward Elementary School - Bus Parking (C-300 to C-301)				
2	Remove Existing Asphalt and 2" of ABC Stone	SY	1,900	
3	Demo Curb	LF	731	
4	Demo Wheel Stops	LS	1	
5	Misc. Sitework for Reconfigured Island	LS	1	
6	3" Asphalt Paving (S9.5C in two lifts)	SY	1,900	
7	Proposed 6" of CABC Stone and 3" of S9.5C Asphalt	SY	255	
8	18" Concrete Curb and Gutter	LF	420	
9	6" Thick Concrete Apron (4,000 psi)	SY	3	
10	Paint Striping	LS	1	
11	6" Extruded Asphalt Curb	LF	200	
<b>SUBTOTAL</b>				

Upward Elementary School - Rear Parking (C-302)				
12	Remove Existing Asphalt and 2" ABC Stone	SY	1,280	
13	3" Asphalt Paving (S9.5C)	SY	1,280	
14	Paint Striping (Match Existing)	LS	1	
<b>SUBTOTAL</b>				

**Upward Elementary School (Item #1)**

**Upward Elementary School Bus Parking - (Items #2-#11)** \_\_\_\_\_

**Upward Elementary School Rear Parking - (Items #12-#14)** \_\_\_\_\_

**GRAND TOTAL (Items #1-#14)** \_\_\_\_\_

**NOTES:**

- 1 Price for patching including asphalt removal should include disposal of waste material off site at an approved location.
- 2 **All items quantities are approximate & shall be verified by contractor prior to bidding.**
- 3 The Owner will be responsible for all testing.
- 4 NCDOT standards shall apply to all work.
- 5 All improved asphalt areas with existing asphalt paint shall be reapplied with paint striping to match existing layout with two coats of asphalt paint unless otherwise specified on plans.