

## **Addendum #1 Campus Wide Site Lighting (Phase 2)**

Sims Engineering email & phone #

[derek@simsengineers.com](mailto:derek@simsengineers.com)

Office: 828.251.2025

Cell: 828.774.3126

Alternate #2 should read:

Replacing the (5) blue circles #28-32 which denote existing poles & lights to include the concrete base if required.

Underground conduit is to be 1 ½" per Sims engineered drawings.

Contractor is to protect payment in the dumpster & laydown area with plywood to protect the new asphalt from damage