

HENDERSON COUNTY PUBLIC SCHOOLS
2026 Paving, Pavement Repairs, Resurfacing, & Striping
Bid Form

Bidder _____

Plans: Henderson County Public Schools 2026 Paving

Bids Due: May 7, 2025

Receipt of the following **addenda** is hereby acknowledged:

Addendum No.	Addendum Date	
_____	_____	
_____	_____	
_____	_____	

No.	DESCRIPTION	UNIT	QTY	UNIT PRICE	TOTAL PRICE
Apple Valley Middle School Base Bid (C-200)					
1	Full Depth Patch	SY	806		
SUBTOTAL					
Apple Valley Middle School Base Bid (C-201)					
2	Existing Asphalt Removal	SY	4,115		
3	3" Asphalt (S9.5C)	SY	4,115		
4	Broom & Sweep Curbs	LS	1		
5	Re-Stripe Parking Lot	LS	1		
SUBTOTAL					
North Henderson High School Base Bid (C-301)					
6	Existing Asphalt Removal	SY	2,360		
7	3" Asphalt (S9.5C)	SY	2,360		
8	Broom & Sweep Curbs	LS	1		
9	Re-Stripe Parking Lot	LS	1		
SUBTOTAL					
North Henderson High School Base Bid (C-302)					
10	Full Depth Patch	SY	77		
SUBTOTAL					
North Henderson Alternate #1 (C-300)					
11	Existing Asphalt Removal	SY	14,320		
12	3" Asphalt (S9.5C)	SY	14,320		
13	Broom & Sweep Curbs	LS	1		
14	Re-Stripe Parking Lot	LS	1		
SUBTOTAL					
North Henderson Alternate #2 (C-300)					
15	Crack Seal	LS	1		
16	Split Seal	SY	14,320		
17	Fog Seal	SY	14,320		
18	Broom & Sweep Curbs	LS	1		
19	Re-Stripe Parking Lot	LS	1		
SUBTOTAL					

Rugby Middle School Alternate #3 (C-400)				
20	Full Depth Patch	SY	39	
21	Remove & Replace Wheel Stops	EA	23	
22	Adjust Utilities	LS	1	
23	Profile Milling	LS	1	
24	Split Seal	SY	5,250	
25	1.5" Asphalt Overlay (S9.5C)	SY	5,250	
26	Re-Stripe Parking Lot	LS	1	
				SUBTOTAL

Rugby Middle School Alternate #4 (C-401)				
27	Existing Asphalt Removal	SY	5,250	
28	Remove Existing Asphalt Curb	LF	1,045	
29	Remove & Replace Wheel Stops	EA	23	
30	Reconditioned ABC Stone	TN	275	
31	Proposed 6-inch Machined Asphalt Curb w/ Backfill	LF	1,045	
32	3" Asphalt (S9.5C)	SY	5,250	
33	Profile Milling	LS	1	
34	Re-Stripe Parking Lot	LS	1	
				SUBTOTAL

BASE BID TOTAL (Items #1- #10) _____

Performance & Payment Bonds (Base Bid Amount - Items #1-#10) _____

BASE BID GRAND TOTAL (Bid + P&P Bonds) _____

Alternate #1 Total = (Subtotal + P&P Bonds) _____

Alternate #2 Total = (Subtotal + P&P Bonds) _____

Alternate #3 Total = (Subtotal + P&P Bonds) _____

Alternate #4 Total = (Subtotal + P&P Bonds) _____

NCDOT Asphalt Index Information (\$/Liquid Ton) _____

Anticipated Construction Start Date _____

Anticipated Construction Duration _____

Subcontractors to be Used:

Company Name	Description of Work
_____	_____
_____	_____
_____	_____
_____	_____

- NOTES:
- Price for patching including asphalt removal should include disposal of waste material off site at an approved location.
 - All items quantities are approximate & shall be verified by contractor prior to bidding.**
 - The Owner will be responsible for all testing.
 - NCDOT standards shall apply to all work.
 - All improved asphalt areas with existing asphalt paint shall be reapplied with paint striping to match existing layout with two coats of asphalt paint.
 - All utilities (valve boxes, manholes, etc.) are to be protected during construction and returned to finished grade as an incidental cost to the project.