

REQUEST FOR COMMITTEE ACTION

HENDERSON COUNTY TECHINICAL REVIEW COMMITTEE

MEETING DATE: November 16, 2021

SUBJECT: Combined Master and Phase I Development Plan for Rich Mountain Major Subdivision (2021-M09)

STAFF CONTACT: Matt Champion, Zoning Administrator

ATTACHMENTS: 1. Staff Report
2. Combined Master & Phase I Development Plan

SUMMARY OF REQUEST:

A subdivision application was submitted on behalf of property owners Robert T. Love, Karen Michelle Maynor, and Tracy Millar on November 1, 2021 by Ripple Falls, LLC. The application is for a Combined Master and Phase I Development Plan for Rich Mountain Major Subdivision, consisting of a total of 60 lots for single family dwellings and a total of 12,799 linear feet of new private roadway. The subject area is located off Locust Grove Road (SR 1528) and contains 245.86 acres. Phase I is approximately 82.78 acres and contains 22 single-family lots. The subject area contains all or portions of PINs: 9672-71-2573, 9672-51-2885, 9672-42-0371, 9672-41-0864, 9671-48-5404, and 9672-40-5853.

TECHNICAL REVIEW COMMITTEE ACTION REQUESTED:

Staff has found that the Combined Master and Phase I Development Plan meets the standards of the subdivision regulations of Chapter 42, Henderson County Land Development Code (LDC). Staff recommends the Combined Master Plan and Phase I Development Plan be subject to the developer addressing any issues raised by the TRC and addressing the comments listed in the Staff Report.

Suggested Motion:

I move that the TRC forward the Combined Master and Phase I Development Plan on to the Planning Board for further review as long as they meet all technical requirements based on the Henderson County Land Development Code and recommendations of the Henderson County Comprehensive Plan and any conditions in the staff report or as discussed by the TRC.

Henderson County Planning Department Staff Report

Combined Master and Phase 1 Development Plan Rich Mountain Major Residential Subdivision (2021-M09)

Property Owner(s): Love, Maynor, & Millar

Applicant/Developer: Andy Baker

PINs: 9672-71-2573, 9672-51-2885, 9672-40-5853, 9672-42-0371 & 9672-41-0864


Master & Development Plan Comments:


According to Chapter 42, Henderson County Land Development Code (LDC) §42-341), the purpose of a Master Plan is to provide general information about the proposed development to allow for an assessment of its impact on the orderly growth and development of the County, environmental quality, land values, natural features identified on the site analysis sketch and the County's roads and governmental services. During the review of the Combined the Master and Development Plan, the Technical Review Committee should take into consideration: applicable recommendations of the *Henderson County Comprehensive Plan*, the potential use of the land to be subdivided, and the impact of the subdivision and proposed use whether residential, commercial, or industrial.


When reviewing the Combined Master and Development Plan it is important to consider that, due to severe topographic conditions, inadequate road access, distance from services, unique natural areas, soils that do not easily support soil drainage systems and/or the proximity to existing and incompatible land uses/zoning, all land may not be suitable to be subdivided for the purpose of dense development (LDC §42-75).

Staff has reviewed the submitted Combined Master and Phase 1 Development Plan for the Rich Mountain Major Subdivision, taking into consideration the recommendations of the *Henderson County Comprehensive Plan* and reviewing the plan for conformance with Henderson County Land Development Code. Staff offers the following comments:


Map A: County Context



Map B: Aerial Imagery


Map C: Existing Parcel Map

Map D: County Comprehensive Plan Future Land Use Map



1. **Henderson County Comprehensive Plan (CCP).** The Future Land Use Map of the CCP shows the Subject Area as being located within an area of Conservation and a portion within the Rural Agriculture Area classification.
 - a. **Conservation Area:** “This category includes land areas that are intended to remain largely in their natural state, with only limited development. Such areas should be targeted for protection through regulations and incentives.”
 - b. **Rural Agriculture Area:** “The RAA covers those portions of the county that are predominantly rural and are characterized by low-density residential development with substantial land areas devoted to agriculture and undeveloped lands. Land use policies will seek to retain that character.”

Map E: Official Zoning Map




2. **Chapter 42, Henderson County Land Development Code (LDC).** According to Chapter 42, Henderson County Land Development Code (LDC) and its Official Zoning Map adopted September 19, 2007 (as amended); the proposed project site is located within the Residential Three (R3) Zoning District.

- Residential Three (R3):** “The purpose of Residential District Three (R3) is to foster orderly growth where the *principal use* of land is low density residential. The intent of this district is to allow for *residential development* consistent with the recommendations of the *Comprehensive Plan*. This general *use district* is typically meant to be utilized in areas designated as Rural (RAA) in the *Comprehensive Plan*.
 - R3 allows for a standard density of 0.66 units per acre. For tracts of land with slopes of 60% or greater that account for 10% or more of the tract, the density shall be $\frac{1}{2}$ the eligible density. The total area of property with slopes of 60% or greater is 16.76 acres or 6.82%.
 - The overall density for the proposed Rich Mountain Major Subdivision is 0.244 units per acre. The proposed density for Phase 1 is 0.26 units per acre.

3. Water and Sewer Availability. The applicant proposes the use of individual water and septic systems for each lot in the subdivision. The applicant has hired a licensed soil scientist to perform a soil evaluation.

4. Road System: The subdivision will be served by private roads built in accordance with the Subdivision Local Road standards required in the LDC. The total linear footage of new roads proposed within the subdivision is 9,856 linear feet and 2,934 linear feet off-site to access the property. Road profiles on the attached plan specify that the maximum grade does not exceed 18% on any of the proposed roads. The primary access will be a private 50' right-of-way with a paved 20' wide road and 4' shoulders. The subdivision collector road will access Locust Grove Road (SR 1528). Phase 1 consists of 3,654 linear feet of private roads within the subdivision to access 22 lots. The applicant will be required to submit a list of proposed road names to the Property Addressing Coordinator for all proposed new roads.

Map F: Streams and Protected Ridges



5. Protected Ridges: The project site is encumbered by the protected ridges buffer. Section §42-252 of the LDC regulates the construction and permitting of “tall buildings” within the protected ridge buffer.

- a. "Tall buildings or structures" include any building, structure or unit within a multiunit building with a vertical height of more than 40 feet measured from the top of the foundation of said building, structure or unit and the uppermost point of said building, structure or unit; provided, however, that where such foundation measured from the natural finished grade of the crest or the natural finished grade of the high side of the slope of a ridge exceeds 3 feet, then such measurement in excess of 3 feet shall be included in the 40-foot limitation described herein; provided, further, that no such building, structure or unit shall protrude at its uppermost point above the crest of the ridge by more than 35 feet.
- b. The site is partially encumbered by several perennial streams. The applicant is required to setback 30' from the edge of surface water.


6. Total Project Proposal Summary:

- 60 single-family lots (22 Lots in Phase 1)
- Total subject area is 245.86 acres (82.78 acres in Phase 1)
- Overall density of 0.244 units/acre (0.26 units/acre in Phase 1)
- Smallest lot is 1.86 acres
- Property Steeper than 60% is 6.82% (16.76 acres)
- Proposed common open space is 79.63 acres (16.89 acres in Phase 1)
- 4,271LF of private roadway
- Individual well and septic systems
- Gated Entrance

Master & Development Plan Comments:

1. **Soil Erosion and Sedimentation Control Plan.** The Applicant shall submit written notice from the appropriate local agencies verifying that an Erosion and Sedimentation Control Plan has been received or a written notice from a professional land surveyor, engineer, landscape architect, architect, or professional planner certifying that no plan is required (LDC §42-95B).
2. **Water Quality.** The Applicant shall submit written notice from the appropriate local agencies verifying that a Stormwater Management Permit has been received (LDC §42-95E).
3. **Private Roads.** Private roads shall be constructed in accordance with the Private Subdivision Local Road standards stated in Chapter 42 (LDC§42-109). Additionally, subdivisions of 35 or more lots shall provide a minimum of two entrance roads. The second entrance road may be specifically waived by the approving authority where unique circumstances exist (LDC §42-95A (1)).
4. **Street Tree Requirements.** According to the street tree requirements of Chapter 42 (LDC §42-95H) the applicant must provide one tree per 50 linear feet of property abutting an internal road. Trees may be placed in groups with a minimum spacing of no less than 15 feet and a maximum spacing of no more than 65 feet. The trees may be placed within the right-of-way or within 20 feet of the edge of the right-of-way. The applicant may use existing trees in accordance with LDC §42-185 instead of planting new trees. These existing trees must also be located within the right-of-way or 20 feet off the edge of the right-of-way as required by LDC §42-185.

5. **Shoulder Stabilization.** All areas disturbed by the construction of a public road, including cut and fill slopes, shoulders and ditch banks, shall be seeded to stabilize the soil and prevent erosion. Seeding should be done as soon as feasible after road construction (LDC §42-102).
6. **Road Drainage, Culverts and Shoulder Stabilization.** Road or drainage structures shall be constructed in accordance with state roads standards. Road drainage side ditches shall be constructed with sufficient depth and width to carry the expected volume of storm water runoff (LDC §42-100). All areas disturbed by the construction of a public road, including cut and fill slopes, shoulders and ditch banks, shall be seeded to stabilize the soil and prevent erosion. Seeding should be done as soon as feasible after road construction (LDC §42-105).
7. **Dead Ends, Cul-de-sacs and Turnarounds.** The Applicant proposes two (2) cul-de-sacs or turnarounds located at the ends of both local roads. All turnarounds must meet of the LDC §42-105 C(8).
8. **Road Name Approval.** Proposed road names for a private and/or public road shall be preapproved by Henderson County in accordance with Chapter 42 of the Henderson County Code, Property Addressing (LDC §42-103). The names of the proposed roads and easements should be confirmed with the development plan approval.
9. **Road Name Signs and Regulatory Signs.** Road name signs and regulatory signs shall be provided in accordance with Chapter 142 of the Henderson County Code. Road name signs and regulatory signs must be acquired and installed prior to final plat approval (LDC §42-104).
10. **Perennial and Intermittent Surface Water Buffer.** All built-upon area shall be a minimum of 30 feet landward of all perennial and intermittent surface water, as defined in LDC §42-251.
11. **Miscellaneous Advisory Provisions.** The Applicant should become familiar with the Miscellaneous Advisory Provisions of Chapter 42 (LDC §42-87).
12. **Final Plat Requirements.** The Final Plat(s) must meet the requirements provided by the Planning Department whenever a subdivision of land occurs (LDC §42-343).
13. **NCDOT Driveway Permit.** An NCDOT Driveway Permit is required for the proposed private, paved road, to access the site. Design should meet requirements of NCDOT.

**SITE AND ZONING NOTES**

PROPERTY ZONING: R3
PROPERTY SIZE: PH1: 82.78 - TOTAL: 245.86 AC.
PROPERTY STEEPER THAN 60%: 16.76 AC (6.82%)

MINIMUM LOT SIZE: 1.50 AC / 35,640 SQ.FT.

SMALLEST PROPOSED LOT: 1.86 ACRES / 80,936 SQ.FT.

MINIMUM LOT WIDTH: 30' @ R.O.W.

MAXIMUM BUILDING HEIGHT: 40'

SETBACKS:

FRONT: 15' (LOCAL)
REAR: 15'
SIDE: 15'

PROPOSED LINEAR FEET OF ROAD:
PHASE 1: 2,388 LF
TOTAL ON PROPERTY: 9,856 LF
OFF PROPERTY EASEMENT: 3,452 LF

*ALL DIMENSIONS ARE FROM EDGE OF
ASPHALT, FACE OF CURB, FACE OF WALL,
OR FACE OF BUILDING UNLESS OTHERWISE
NOTED.

*ALL CONSTRUCTION SHALL BE IN
ACCORDANCE WITH THE LATEST EDITION OF
DETAILS, SPECIFICATIONS, AND OTHER
DEVELOPMENT ORDINANCES OF HENDERSON CO.

DEVELOPMENT DATA

PROPERTY ADDRESS: LOCUST GROVE ROAD
HENDERSONVILLE NC
PIN NUMBER: 9672712573, 9672512885, 967240371
9672410864, 9671485404, 967240583

PROPERTY SIZE: PH1: 82.78 AC - TOTAL: 245.86 AC
ZONING REVIEW: HENDERSON COUNTY
EROSION CONTROL REVIEW: HENDERSON COUNTY
STORMWATER REVIEW: HENDERSON COUNTY

ZONING CLASSIFICATION: R3

PROPOSED NUMBER OF UNITS: PH1: 22 - TOTAL: 60

PROPOSED DENSITY: PH1: 0.26 LOTS/AC - TOTAL: 0.244 LOTS / AC

PROPOSED LINEAR FEET OF ROAD: PHASE 1: 3,654 LF
TOTAL ON PROPERTY: 9,856 LF
OFF PROPERTY EASEMENT: 2,934 LF

LOTS 1-51 ARE LOCATED IN A FARMLAND PRESERVATION DISTRICT. LOTS
52-60 ARE WITHIN 1/2 MILE OF THE FARMLAND PRESERVATION
DISTRICT

WATER AND SEWER WILL BE PROVIDED BY INDIVIDUAL WELLS AND SEPTIC
SYSTEMS



PUBLIC WATER AND SEWER ARE APPROXIMATELY 3.0 MILES FROM THE SITE
DRY HYDRANT IS LOCATED APPROXIMATELY 0.90 ROAD MILES FROM THE
ENTRANCE TO THE SITE

PROPERTY OWNER: MULTIPLE OWNERS -
SEE SHEET C-0
FOR CONTACT INFORMATION

DEVELOPER: RIPPLE FALLS LLC
CONTACT: ANDY BAKER
ADDRESS: 69 CLARK GAP ROAD
FLETCHER NC

EMAIL: ANDY@TFMCAROLINA.COM
PHONE: (616) 402-0367

ENGINEER: BROOKS ENGINEERING
CONTACT: WYATT EDESEL PE
ADDRESS: 15 ARLINGTON ST
ASHEVILLE, NC 28801
EMAIL: WEDSEL@BROOKSEA.COM
PHONE: 828-232-4700




| CLEARING AND GRUBBING LEGEND | |
|------------------------------------|--|
| EXIST. BOUNDARY | |
| EXIST. ADJOINER | |
| EXIST. STREAM | |
| EXIST. STREAM BUFFER | |
| EXIST. WETLAND | |
| EXIST. FEMA NON-ENROACHMENT | |
| FEMA FLOOD HAZARD AREA (1%) | |
| FEMA FLOOD HAZARD AREA (0.2%) | |
| EXIST. RIGHT OF WAY | |
| EXIST. MANHOLE | |
| EXIST. SANITARY SEWER | |
| EXIST. OVERHEAD UTILITIES | |
| EXIST. STORM DRAIN | |
| EXIST. MINOR CONTOUR | |
| EXIST. MAJOR CONTOUR | |
| EXIST. DROP INLET | |
| EXIST. CURB INLET | |
| EXIST. JUNCTION BOX | |
| TEMP. SILT FENCE | |
| TEMP. TREE PROTECTION FENCE | |
| TEMP. CONSTRUCTION ENTRANCE | |
| LIMITS OF DISTURBANCE | |
| TEMP. REINFORCED STABILIZED OUTLET | |
| TEMP. SEDIMENT BASIN BAFFLES | |
| TEMP. SEDIMENT BASIN | |
| TEMP. DIVERSION DITCH | |
| TEMP. SLOPE MATTING | |
| DEMO BUILDING | |
| DEMO CONCRETE | |
| DEMO PAVEMENT | |
| DEMO GRAVEL | |
| DEMO CURB | |
| DEMO SANITARY SEWER | |
| DEMO WATER LINE | |
| DEMO OTHER UTILITIES | |
| DEMO STORM DRAIN | |


EROSION CONTROL NOTES


- ALL EROSION MEASURES AND PRACTICES SHALL BE IN ACCORDANCE WITH THE APPROPRIATE JURISDICTION'S DETAILS AND SPECIFICATIONS.
- IN ACCORDANCE WITH THE NPDES GENERAL STORMWATER PERMIT, THE FOLLOWING CONDITIONS MUST BE MET:
- THE EROSION CONTROL PLAN MUST BE IMPLEMENTED - DEVIATIONS ARE A VIOLATION OF THE PERMIT
- A COPY OF ALL PLANS MUST BE RETAINED BY THE PERMIT
- DEPOSITION OF SEDIMENT OFFSITE OR IN A STREAM OR WETLAND ARE CONSIDERED A VIOLATION OF THE PERMIT.
- VISIBLE DEPOSITION OF SEDIMENT SHALL BE REPORTED TO NCDEQ WITHIN 24 HOURS OF INSPECTION.
- A RAIN GAUGE SHALL BE MAINTAINED ON SITE.
- A WRITTEN RECORD OF THE DAILY RAINFALL AMOUNTS SHALL BE RETAINED.
- AT LEAST ONCE PER WEEK, EACH EROSION CONTROL MEASURE SHALL BE INSPECTED TO ENSURE THAT IT IS OPERATING CORRECTLY AND RECORDS MAINTAINED.
- INSPECTIONS SHALL ALSO BE MADE WITHIN 24 HOURS OF RAIN EVENTS OVER 1/2 INCH.
- THE QUALITY OF ALL STORMWATER DISCHARGES SHALL BE OBSERVED AND RECORDED.
- IF ANY VISIBLE SEDIMENTATION IS LEAVING THE SITE OR ENTERING WATERS OF THE STATE, CORRECTIVE ACTION SHALL BE TAKEN IMMEDIATELY TO CONTROL THE DISCHARGE OF SEDIMENTS.
- AN APPROVED COPY OF THE EESC PLAN WITH PLACARD AND APPROVAL LETTER AND A COPY OF THE NPDES PERMIT, WITH A MINIMUM OF 30 DAYS OF SELF-INSPECTION REPORTS, ARE TO BE KEPT ON SITE UNTIL PROJECT CLOSURE BY NCDEQ. THEY MUST BE MADE AVAILABLE TO THE EROSION CONTROL CONTRACTOR UPON REQUEST.
- THE E INSPECTION LOGS ARE TO BE SEPARATE FROM THE WEEKLY SELF-MONITORING PROGRAM OF THE NPDES STORMWATER PERMIT FOR CONSTRUCTION ACTIVITIES. CONTRACTOR SHALL USE THE INSPECTION AND MONITORING RECORDS FOR ACTIVITIES UNDER STORMWATER GENERAL PERMIT NCG01000 AND SELF-INSPECTION RECORDS FOR LAND DISTURBING ACTIVITIES PER G.S. 13A-54.1. THE INSPECTIONS SHOULD BE CONDUCTED AFTER EACH PHASE OF THE PROJECT, AND CONTINUED UNTIL PERMANENT GROUND COVER IS ESTABLISHED.
- ALL DRAINAGE EASEMENTS MUST BE GRASSED AND/OR RIP-RAPPED PER THE PLANS TO CONTROL EROSION.
- THE ESCAPE OF SEDIMENT FROM THE SITE SHALL BE PREVENTED BY THE INSTALLATION OF EROSION AND SEDIMENT CONTROL MEASURES AND PRACTICES PRIOR TO, OR CONCURRENT WITH, LAND-DISTURBING ACTIVITIES.
- EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE AND AN AMENDED PLAN BE SUBMITTED AND APPROVED SHOWING MODIFIED EROSION CONTROL DEVICES.
- A RAIN GAUGE WILL BE INSTALLED ON THE SITE.
- THE SITE SHALL RECEIVE TEMPORARY/PERMANENT SEEDING WHEN CONSTRUCTION IS COMPLETE OR DELAYED FOR ANY REASON. SEE SHEET C-5.7 FOR A DETAILED TIME FRAME.
- CONTRACTOR TO PROVIDE INLET PROTECTION AT EACH STRUCTURE AS STATED IN SYSTEM CONTRACT.
- PROVIDE MORTAR-JOINTS ON ANY STORM DRAINS WHERE VELOCITIES EXCEED 15 FT/SEC (SEE PIPE CHART).
- STOCKPILE STAGING, AND LAYDOWN AREAS ARE TO BE WITHIN THE LIMITS OF DISTURBANCE AND SHOULD BE LOCATED AT LEAST 50 FEET AWAY FROM STORM DRAIN OUTLETS AND SURFACE WATERS.

| DEVELOPMENT DATA | |
|---|--|
| PROPERTY ADDRESS: | LOCUST GROVE ROAD HENDERSONVILLE NC |
| PIN NUMBER: | 9672712573 9672512885 967240371 9672410864 9671485404 967240583 |
| PROPERTY SIZE: | PH1: 82.78 AC - TOTAL: 245.86 AC |
| ZONING REVIEW: | HENDERSON COUNTY |
| EROSION CONTROL REVIEW: | HENDERSON COUNTY |
| STORMWATER REVIEW: | HENDERSON COUNTY |
| ZONING CLASSIFICATION: | R3 |
| PROPOSED NUMBER OF UNITS: | PH1: 22 - TOTAL: 60 |
| PROPOSED DENSITY: | PH1: 0.26 LOTS/AC - TOTAL: 0.244 LOTS / AC |
| PROPOSED LINEAR FEET OF ROAD: | PHASE 1: 3,654 LF TOTAL ON PROPERTY: 9,856 LF |
| | OFF-PROPERTY EASEMENT: 2,934 LF |
| LOTS 1-51 ARE LOCATED IN A FARMLAND PRESERVATION DISTRICT, LOTS 52-60 ARE WITHIN 1/2 MILE OF A THE FARMLAND PRESERVATION DISTRICT | |
| WATER AND SEWER WILL BE PROVIDED BY INDIVIDUAL WELLS AND SEPTIC SYSTEMS | |
| PUBLIC WATER AND SEWER ARE APPROXIMATELY 3.0 MILES FROM THE SITE | |
| DRY HYDRANT IS LOCATED APPROXIMATELY 0.90 ROAD MILES FROM THE ENTRANCE TO THE SITE | |
| PROPERTY OWNER: | MULTIPLE OWNERS - SEE SHEET C-0 FOR CONTACT INFORMATION |
| DEVELOPER: | ripple falls llc |
| CONTACT: | andy baker |
| ADDRESS: | 69 CLARK GAP ROAD FLETCHER NC |
| EMAIL: | ANDY@TFMCAROLINA.COM |
| PHONE: | (616) 402-0367 |
| ENGINEER: | BROOKS ENGINEERING |
| CONTACT: | WYATT EDSLE PE |
| ADDRESS: | 15 ARLINGTON ST ASHEVILLE, NC 28801 |
| EMAIL: | WEDSEL@BROOKSEA.COM |
| PHONE: | 828-232-4700 |



SCALE: 1" = 300



**SITE AND ZONING NOTES**

PROPERTY ZONING: R3
PROPERTY SIZE: PH1: 82.78 - TOTAL: 245.86 AC.
PROPERTY STEEPER THAN 60%: 16.76 AC (6.82%)

MINIMUM LOT SIZE: 1.50 AC / 35,640 SQ.FT.
SMALLEST PROPOSED LOT: 1.86 ACRES / 80,936 SQ.FT.

MINIMUM LOT WIDTH: 30' @ R.O.W.

MAXIMUM BUILDING HEIGHT: 40'

SETBACKS:

FRONT: 15' (LOCAL)

REAR: 15'

SIDE: 15'

PROPOSED LINEAR FEET OF ROAD:

PHASE 1: 2,394 LF

TOTAL ON PROPERTY: 9,856 LF

OFF PROPERTY EASEMENT: 3,452 LF

*ALL DIMENSIONS ARE FROM EDGE OF ASPHALT, FACE OF CURB, FACE OF WALL, OR FACE OF BUILDING UNLESS OTHERWISE NOTED.

*ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF DETAILS, SPECIFICATIONS, AND OTHER DEVELOPMENT ORDINANCES OF HENDERSON CO.

DEVELOPMENT DATA

PROPERTY ADDRESS: LOCUST GROVE ROAD
HENDERSONVILLE NC
PIN NUMBER: 9672712573, 9672512885, 967240371
9672410864, 9671485404, 967240583

PROPERTY SIZE: PH1: 82.78 AC - TOTAL: 245.86 AC
ZONING REVIEW: HENDERSON COUNTY
EROSION CONTROL REVIEW: HENDERSON COUNTY

STORMWATER REVIEW: HENDERSON COUNTY
ZONING CLASSIFICATION: R3

PROPOSED NUMBER OF UNITS: PH1: 22 - TOTAL: 60

PROPOSED DENSITY: PH1: 0.26 LOTS/AC - TOTAL: 0.244 LOTS / AC

PROPOSED LINEAR FEET OF ROAD: PHASE 1: 3,654 LF

TOTAL ON PROPERTY: 9,856 LF

OFF PROPERTY EASEMENT: 2,934 LF

LOTS 1-51 ARE LOCATED IN A FARMLAND PRESERVATION DISTRICT, LOTS 52-60 ARE WITHIN 1/2 MILE OF A THE FARMLAND PRESERVATION DISTRICT

WATER AND SEWER WILL BE PROVIDED BY INDIVIDUAL WELLS AND SEPTIC SYSTEMS

PUBLIC WATER AND SEWER ARE APPROXIMATELY 3.0 MILES FROM THE SITE

DRY HYDRANT IS LOCATED APPROXIMATELY 0.90 ROAD MILES FROM THE ENTRANCE TO THE SITE

PROPERTY OWNER: MULTIPLE OWNERS -
SEE SHEET C-0
FOR CONTACT INFORMATION

DEVELOPER: RIPPLE FALLS LLC

CONTACT: ANDY BAKER

ADDRESS: 69 CLARK GAP ROAD

FLETCHER NC

EMAIL: ANDY@TFMCAROLINA.COM

PHONE: (616) 402-0367

ENGINEER: BROOKS ENGINEERING

CONTACT: WYATT EDSPEL PE

ADDRESS: 15 ARLINGTON ST


ASHEVILLE, NC 28801


EMAIL: WEDSEL@BROOKSEA.COM

PHONE: 828-232-4700



0 300 600 900
SCALE: 1" = 300



**SITE AND ZONING NOTES**

PROPERTY ZONING: R3
PROPERTY SIZE: PH1: 82.78 - TOTAL: 245.86 AC.
PROPERTY STEEPER THAN 60%: 16.76 AC (6.82%)

MINIMUM LOT SIZE: 1.50 AC / 35,640 SQ.FT.
SMALLEST PROPOSED LOT: 1.86 ACRES / 80,936 SQ.FT.

MINIMUM LOT WIDTH: 30' @ R.O.W.

MAXIMUM BUILDING HEIGHT: 40'

SETBACKS:

FRONT: 15' (LOCAL)
REAR: 15'
SIDE: 15'

PROPOSED LINEAR FEET OF ROAD:
PHASE 1: 2,394 LF
TOTAL ON PROPERTY: 9,856 LF
OFF PROPERTY EASEMENT: 3,452 LF

*ALL DIMENSIONS ARE FROM EDGE OF
ASPHALT, FACE OF CURB, FACE OF WALL,
OR FACE OF BUILDING UNLESS OTHERWISE
NOTED.

*ALL CONSTRUCTION SHALL BE IN
ACCORDANCE WITH THE LATEST EDITION OF
DETAILS, SPECIFICATIONS, AND OTHER
DEVELOPMENT ORDINANCES OF HENDERSON CO.

DEVELOPMENT DATA

PROPERTY ADDRESS: LOCUST GROVE ROAD
HENDERSONVILLE NC
PIN NUMBER: 9672712573, 9672512885, 967240371
9672410864, 9671485404, 967240583

PROPERTY SIZE: PH1: 82.78 AC - TOTAL: 245.86 AC
ZONING REVIEW: HENDERSON COUNTY
EROSION CONTROL REVIEW: HENDERSON COUNTY

STORMWATER REVIEW: HENDERSON COUNTY

ZONING CLASSIFICATION: R3

PROPOSED NUMBER OF UNITS: PH1: 22 - TOTAL: 60

PROPOSED DENSITY: PH1: 0.26 LOTS/AC - TOTAL: 0.244 LOTS / AC

PROPOSED LINEAR FEET OF ROAD: PHASE 1: 3,654 LF
TOTAL ON PROPERTY: 9,856 LF
OFF PROPERTY EASEMENT: 2,934 LF

LOTS 1-51 ARE LOCATED IN A FARMLAND PRESERVATION DISTRICT, LOTS
52-60 ARE WITHIN 1/2 MILE OF A THE FARMLAND PRESERVATION
DISTRICT

WATER AND SEWER WILL BE PROVIDED BY INDIVIDUAL WELLS AND SEPTIC
SYSTEMS


PUBLIC WATER AND SEWER ARE APPROXIMATELY 3.0 MILES FROM THE SITE
DRY HYDRANT IS LOCATED APPROXIMATELY 0.90 ROAD MILES FROM THE
ENTRANCE TO THE SITE

PROPERTY OWNER: MULTIPLE OWNERS -
SEE SHEET C-0
FOR CONTACT INFORMATION

DEVELOPER: RIPPLE FALLS LLC
CONTACT: ANDY BAKER
ADDRESS: 69 CLARK GAP ROAD
FLETCHER NC

EMAIL: ANDY@TFMCAROLINA.COM
PHONE: (616) 402-0367

ENGINEER: BROOKS ENGINEERING
CONTACT: WYATT EDSEL PE
ADDRESS: 15 ARLINGTON ST
ASHEVILLE, NC 28801
EMAIL: WEDSEL@BROOKSEA.COM
PHONE: 828-232-4700



SHEET C-4.2

PROPOSED EASEMENT (TYP)

PROPOSED 45FT RIGHT OF WAY (TYP)

PROPOSED 20FT PAVED ROAD (TYP) (SEE SHEET C-4.14)

EXISTING 50FT RIGHT OF WAY (TYP)

LOCUST GROVE ROAD - SR 1528
(50' PUBLIC R.O.W. ASPHALT)

JOHNSON, BETTY JO
DB: 846, PG: 357
PIN: 9671692038

| | | | |
|--|-----------------------------------|--|------------|
| Project No: 543521 | RICH MOUNTAIN SUBDIVISION PHASE 1 | REVISIONS/SUBMISSIONS | |
| C-4.1 | RESIDENTIAL SUBDIVISION | No. | Date |
| HENDERSON COUNTY | NORTH CAROLINA | 1 | 11-02-2021 |
| Reviewed: WB Drawn: AS NOTED Checked: WE Date: 2021-11-02 | | Reviewed: WB Drawn: AS NOTED Checked: WE Date: 2021-11-02 | |
| BROOKS ENGINEERING ASSOCIATES Asheville, NC 28801 Phone: 1-828-232-4700 Fax: 1-828-232-1331 www.brooksea.com | | BROOKS ENGINEERING ASSOCIATES Planning • Engineering • Surveying • Environmental Services • | |
| PRELIMINARY - NOT FOR CONSTRUCTION | | | |

| <u>SITE PLAN LEGEND</u> | |
|-------------------------|-------------------------------|
| — | EXIST. BOUNDARY |
| - - - | EXIST. ADJOINER |
| - - - - | EXIST. STREAM |
| - - - - | EXIST. STREAM BUFFER |
| - - - - | EXIST. WETLAND |
| [] | EXIST. FEMA NON-ENCROACHMENT |
| | FEMA FLOOD HAZARD AREA (1%) |
| | FEMA FLOOD HAZARD AREA (0.2%) |
| — — — | EXIST. RIGHT OF WAY |
| — — — | EXIST. BUILDING SETBACK |
| [] | EXIST. BUILDING |
| — | EXISTING SIDEWALK |
| — | EXISTING PAVEMENT |
| — | EXIST. CURB |
| — — — | NEW PROPERTY LINES |
| — — — | NEW RIGHT OF WAY |
| — — — | NEW EASEMENT |
| — — — | BUILDING SETBACK LINE |
| — — — | NEW LANDSCAPE BUFFER |
| — | NEW COMMON OPEN SPACE |
| — | NEW BUILDING |
| — | NEW PAVEMENT |
| — | NEW HD PAVEMENT |
| — | NEW CONCRETE SIDEWALK |
| — | NEW GRAVEL |
| — | NEW CURB & GUTTER |
| — | NEW WALL (BY OTHERS) |

SITE AND ZONING NOTES

PROPERTY ZONING: R3
PROPERTY SIZE: PH1: 82.78 - TOTAL: 245.86 AC.
PROPERTY STEEPER THAN 60%: 16.76 AC (6.82%)

MINIMUM LOT SIZE: 1.50 AC / 35,640 SQ.FT.
SMALLEST PROPOSED LOT: 1.86 ACRES / 80,936 SQ.FT.

MINIMUM LOT WIDTH: 30' @ R.O.W.

MAXIMUM BUILDING HEIGHT: 40'

SETBACKS:

FRONT: 15' (LOCAL)

REAR: 15'

SIDE: 15'

PROPOSED LINEAR FEET OF ROAD:
PHASE 1: 2,394 LF
TOTAL ON PROPERTY: 9,856 LF
OFF PROPERTY EASEMENT: 3,452 LF

*ALL DIMENSIONS ARE FROM EDGE OF
ASPHALT, FACE OF CURB, FACE OF WALL,
OR FACE OF BUILDING UNLESS OTHERWISE
NOTED.

*ALL CONSTRUCTION SHALL BE IN
ACCORDANCE WITH THE LATEST EDITION OF
DETAILS, SPECIFICATIONS, AND OTHER
DEVELOPMENT ORDINANCES OF HENDERSON CO.

DEVELOPMENT DATA

PROPERTY ADDRESS: LOCUST GROVE ROAD
HENDERSONVILLE NC
PIN NUMBER: 9672712573, 9672512885, 967240371
9672410864, 9671485404, 967240583

PROPERTY SIZE: PH1: 82.78 AC - TOTAL: 245.86 AC
ZONING REVIEW: HENDERSON COUNTY
EROSION CONTROL REVIEW: HENDERSON COUNTY
STORMWATER REVIEW: HENDERSON COUNTY

ZONING CLASSIFICATION: R3
PROPOSED NUMBER OF UNITS: PH1: 22 - TOTAL: 60
PROPOSED DENSITY: PH1: 0.26 LOTS/AC - TOTAL: 0.244 LOTS / AC

PROPOSED LINEAR FEET OF ROAD: PHASE 1: 3,654 LF
TOTAL ON PROPERTY: 9,856 LF
OFF PROPERTY EASEMENT: 2,934 LF

LOTS 1-51 ARE LOCATED IN A FARMLAND PRESERVATION DISTRICT, LOTS
52-60 ARE WITHIN 1/2 MILE OF A THE FARMLAND PRESERVATION
DISTRICT


WATER AND SEWER WILL BE PROVIDED BY INDIVIDUAL WELLS AND SEPTIC
SYSTEMS

PUBLIC WATER AND SEWER ARE APPROXIMATELY 3.0 MILES FROM THE SITE
DRY HYDRANT IS LOCATED APPROXIMATELY 0.90 ROAD MILES FROM THE
ENTRANCE TO THE SITE

PROPERTY OWNER: MULTIPLE OWNERS -
SEE SHEET C-0
FOR CONTACT INFORMATION

DEVELOPER: RIPPLE FALLS LLC
CONTACT: ANDY BAKER
ADDRESS: 69 CLARK GAP ROAD
FLETCHER NC
EMAIL: ANDY@TMFCAROLINA.COM
PHONE: (616) 402-0367

ENGINEER: BROOKS ENGINEERING
CONTACT: WYATT EDSEL PE
ADDRESS: 15 ARLINGTON ST
ASHEVILLE, NC 28801
EMAIL: WEDSEL@BROOKSEA.COM
PHONE: 828-232-4700



LOVE, ROBERT T
DB: 1073, PG: 156
PIN: 9671485404

SHEET C-4.3


PROPOSED EASEMENT (TYP)

PROPOSED 20FT PAVED ROAD (TYP) (SEE SHEET C-4.14)

PROPOSED 45FT RIGHT OF WAY (TYP)

PROPOSED CENTER LINE (TYP)

SHEET C-4.1

| | | | |
|---|--|--|--|
| Project No: 543521 | RICH MOUNTAIN SUBDIVISION PHASE 1 RESIDENTIAL SUBDIVISION HENDERSON COUNTY NORTH CAROLINA | Reviewed: WB Drawn: WB Checked: WB Date: 2021-11-02 | No. 1 HENDERSON COUNTY TRC 11-02-2021 |
| C-4.2 | PRELIMINARY - NOT FOR CONSTRUCTION | | |
|  BROOKS ENGINEERING ASSOCIATES | | Planning • Engineering • Surveying • Environmental Services • | |
| File Location: L:\2021 Projects\543521 Ripple Falls_Rich Mt. Due Diligence\Drawings\Site Plan 2.dwg | | | |

| SITE PLAN LEGEND | |
|-------------------------|-------------------------------|
| — | EXIST. BOUNDARY |
| - - - | EXIST. ADJOINER |
| - - - | EXIST. STREAM |
| - - - | EXIST. STREAM BUFFER |
| - - - | EXIST. WETLAND |
| [] | EXIST. FEMA NON-ENCROACHMENT |
| | FEMA FLOOD HAZARD AREA (1%) |
| | FEMA FLOOD HAZARD AREA (0.2%) |
| - - - | EXIST. RIGHT OF WAY |
| - - - | EXIST. BUILDING SETBACK |
| [] | EXIST. BUILDING |
| [] | EXISTING SIDEWALK |
| [] | EXISTING PAVEMENT |
| — | EXIST. CURB |
| — | NEW PROPERTY LINES |
| — | NEW RIGHT OF WAY |
| — | NEW EASEMENT |
| — | BUILDING SETBACK LINE |
| — | NEW LANDSCAPE BUFFER |
| [] | NEW COMMON OPEN SPACE |
| [] | NEW BUILDING |
| [] | NEW PAVEMENT |
| [] | NEW HD PAVEMENT |
| [] | NEW CONCRETE SIDEWALK |
| [] | NEW GRAVEL |
| [] | NEW CURB & GUTTER |
| [] | NEW WALL (BY OTHERS) |

SITE AND ZONING NOTES

PROPERTY ZONING: R3
PROPERTY SIZE: PH1: 82.78 - TOTAL: 245.86 AC.
PROPERTY STEEPER THAN 60%: 16.76 AC (6.82%)

MINIMUM LOT SIZE: 1.50 AC / 35,640 SQ.FT.
SMALLEST PROPOSED LOT: 1.86 ACRES / 80,936 SQ.FT.

MINIMUM LOT WIDTH: 30' @ R.O.W.

MAXIMUM BUILDING HEIGHT: 40'

SETBACKS:

FRONT: 15' (LOCAL)

REAR: 15'

SIDE: 15'

PROPOSED LINEAR FEET OF ROAD:

PHASE 1: 2,394 LF

TOTAL ON PROPERTY: 9,856 LF

OFF PROPERTY EASEMENT: 3,452 LF

*ALL DIMENSIONS ARE FROM EDGE OF
ASPHALT, FACE OF CURB, FACE OF WALL,
OR FACE OF BUILDING UNLESS OTHERWISE
NOTED.

*ALL CONSTRUCTION SHALL BE IN
ACCORDANCE WITH THE LATEST EDITION OF
DETAILS, SPECIFICATIONS, AND OTHER
DEVELOPMENT ORDINANCES OF HENDERSON CO.

DEVELOPMENT DATA

PROPERTY ADDRESS: LOCUST GROVE ROAD
HENDERSONVILLE NC
PIN NUMBER: 9672712573, 9672512885, 967240371
9672410864, 9671485404, 967240583

PROPERTY SIZE: PH1: 82.78 AC - TOTAL: 245.86 AC
ZONING REVIEW: HENDERSON COUNTY

EROSION CONTROL REVIEW: HENDERSON COUNTY

STORMWATER REVIEW: HENDERSON COUNTY

ZONING CLASSIFICATION: R3

PROPOSED NUMBER OF UNITS: PH1: 22 - TOTAL: 60

PROPOSED DENSITY: PH1: 0.26 LOTS/AC - TOTAL: 0.244 LOTS / AC

PROPOSED LINEAR FEET OF ROAD: PHASE 1: 3,654 LF

TOTAL ON PROPERTY: 9,856 LF

OFF PROPERTY EASEMENT: 2,934 LF

LOTS 1-51 ARE LOCATED IN A FARMLAND PRESERVATION DISTRICT, LOTS
52-60 ARE WITHIN 1/2 MILE OF A THE FARMLAND PRESERVATION
DISTRICT

WATER AND SEWER WILL BE PROVIDED BY INDIVIDUAL WELLS AND SEPTIC
SYSTEMS

PUBLIC WATER AND SEWER ARE APPROXIMATELY 3.0 MILES FROM THE SITE

DRY HYDRANT IS LOCATED APPROXIMATELY 0.90 ROAD MILES FROM THE
ENTRANCE TO THE SITE


PROPERTY OWNER: MULTIPLE OWNERS -
SEE SHEET C-0
FOR CONTACT INFORMATION

DEVELOPER: RIPPLE FALLS LLC
CONTACT: ANDY BAKER
ADDRESS: 69 CLARK GAP ROAD
FLETCHER NC

EMAIL: ANDY@TFMCAROLINA.COM
PHONE: (616) 402-0367

ENGINEER: BROOKS ENGINEERING
CONTACT: WYATT EDESL PE
ADDRESS: 15 ARLINGTON ST
ASHEVILLE, NC 28801

EMAIL: WEDSEL@BROOKSEA.COM
PHONE: 828-232-4700



100+18 Sq. Feet
2.4437 Acres

SHEET C-4.4

N 87°20'28" W

767.0651'

N 87°20'28" W

531.0865'

PROPERTY BOUNDARY (TYP)

PROPOSED ISLAND & GATE (TYP)

LOVE, ROBERT T
DB: 1089, PG: 481
PIN: 9672512885


PROPOSED 20FT PAVED ROAD (TYP) (SEE SHEET C-4.14)

PROPOSED CENTER LINE (TYP)

PROPOSED EASEMENT (TYP)

SHEET C-4.2

| | | | | |
|--|---|--|----------------------------------|---------------------|
| Project No: 543521 | RICH MOUNTAIN SUBDIVISION PHASE 1 HENDERSON COUNTY NORTH CAROLINA | Reviewed: WB Drawn: WB Checked: WB Date: 2021-11-02 | No. 1 HENDERSON COUNTY TRC | Date: 11-02-2021 |
| C-4.3 | RESIDENTIAL SUBDIVISION HENDERSON COUNTY NORTH CAROLINA | PRELIMINARY - NOT FOR CONSTRUCTION | | |
| Drawing Title: SITE PLAN 3 | | BROOKS ENGINEERING ASSOCIATES Planning • Engineering • Surveying • Environmental Services • | | |
| Revision/Submissions number within a triangle indicates changes made on this sheet | | | | |

**SITE AND ZONING NOTES**

PROPERTY ZONING: R3
PROPERTY SIZE: PH1: 82.78 - TOTAL: 245.86 AC.
PROPERTY STEEPER THAN 60%: 16.76 AC (6.82%)

MINIMUM LOT SIZE: 1.50 AC / 35,640 SQ.FT.

SMALLEST PROPOSED LOT: 1.86 ACRES / 80,936 SQ.FT.

MINIMUM LOT WIDTH: 30' @ R.O.W.

MAXIMUM BUILDING HEIGHT: 40'

SETBACKS:

FRONT: 15' (LOCAL)

REAR: 15'

SIDE: 15'

PROPOSED LINEAR FEET OF ROAD:

PHASE 1: 2,394 LF

TOTAL ON PROPERTY: 9,856 LF

OFF PROPERTY EASEMENT: 3,452 LF

*ALL DIMENSIONS ARE FROM EDGE OF ASPHALT, FACE OF CURB, FACE OF WALL, OR FACE OF BUILDING UNLESS OTHERWISE NOTED.

*ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF DETAILS, SPECIFICATIONS, AND OTHER DEVELOPMENT ORDINANCES OF HENDERSON CO.

DEVELOPMENT DATA

PROPERTY ADDRESS: LOCUST GROVE ROAD
HENDERSONVILLE NC
PIN NUMBER: 9672712573, 9672512885, 967240371
9672410864, 9671485404, 967240583

PROPERTY SIZE: PH1: 82.78 AC - TOTAL: 245.86 AC

ZONING REVIEW: HENDERSON COUNTY

EROSION CONTROL REVIEW: HENDERSON COUNTY

STORMWATER REVIEW: HENDERSON COUNTY

ZONING CLASSIFICATION: R3

PROPOSED NUMBER OF UNITS: PH1: 22 - TOTAL: 60

PROPOSED DENSITY: PH1: 0.26 LOTS/AC - TOTAL: 0.244 LOTS / AC

PROPOSED LINEAR FEET OF ROAD: PHASE 1: 3,654 LF

TOTAL ON PROPERTY: 9,856 LF

OFF PROPERTY EASEMENT: 2,934 LF

LOTS 1-51 ARE LOCATED IN A FARMLAND PRESERVATION DISTRICT, LOTS 52-60 ARE WITHIN 1/2 MILE OF A THE FARMLAND PRESERVATION DISTRICT

WATER AND SEWER WILL BE PROVIDED BY INDIVIDUAL WELLS AND SEPTIC SYSTEMS

PUBLIC WATER AND SEWER ARE APPROXIMATELY 3.0 MILES FROM THE SITE

DRY HYDRANT IS LOCATED APPROXIMATELY 0.90 ROAD MILES FROM THE ENTRANCE TO THE SITE

PROPERTY OWNER: MULTIPLE OWNERS - SEE SHEET C-0 FOR CONTACT INFORMATION

DEVELOPER: RIPPLE FALLS LLC

CONTACT: ANDY BAKER

ADDRESS: 69 CLARK GAP ROAD

FLETCHER NC

EMAIL: ANDY@TFMCAROLINA.COM

PHONE: (616) 402-0367

ENGINEER: BROOKS ENGINEERING

CONTACT: WYATT EDSLEPE PE



ADDRESS: 15 ARLINGTON ST

ASHEVILLE, NC 28801

EMAIL: WEDSEL@BROOKSEA.COM


PHONE: 828-232-4700

SHEET C-4.5



SHEET C-4.5

| | | | |
|--|--|--|--|
| Project No: 543521 | | Drawing Title: SITE PLAN 4 | |
| RICH MOUNTAIN SUBDIVISION PHASE 1 RESIDENTIAL SUBDIVISION HENDERSON COUNTY NORTH CAROLINA | | BROOKS ENGINEERING ASSOCIATES Planning • Engineering • Surveying • Environmental Services • | |
| REVISION/SUBMISSIONS No.: 1 Date: 11-02-2021 HENDERSON COUNTY TRC | | PRELIMINARY - NOT FOR CONSTRUCTION | |
| | | | |
| | | | |
| File Location: L:\2021 Projects\543521 Ripple Falls\Rich Mtn. Due Diligence\Drawings\Site Plan 4.dwg File Location: L:\2021 Projects\543521 Ripple Falls\Rich Mtn. Due Diligence\Drawings\Site Plan 4.dwg | | | |

**SITE AND ZONING NOTES**

PROPERTY ZONING: R3
PROPERTY SIZE: PH1: 82.78 - TOTAL: 245.86 AC.
PROPERTY STEEPER THAN 60%: 16.76 AC (6.82%)

MINIMUM LOT SIZE: 1.50 AC / 35,640 SQ.FT.
SMALLEST PROPOSED LOT: 1.86 ACRES / 80,936 SQ.FT.

MINIMUM LOT WIDTH: 30' @ R.O.W.

MAXIMUM BUILDING HEIGHT: 40'

SETBACKS:

FRONT: 15' (LOCAL)

REAR: 15'

SIDE: 15'

PROPOSED LINEAR FEET OF ROAD:

PHASE 1: 2,394 LF

TOTAL ON PROPERTY: 9,856 LF

OFF PROPERTY EASEMENT: 3,452 LF

*ALL DIMENSIONS ARE FROM EDGE OF ASPHALT, FACE OF CURB, FACE OF WALL, OR FACE OF BUILDING UNLESS OTHERWISE NOTED.

*ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF DETAILS, SPECIFICATIONS, AND OTHER DEVELOPMENT ORDINANCES OF HENDERSON CO.

DEVELOPMENT DATA

PROPERTY ADDRESS: LOCUST GROVE ROAD
HENDERSONVILLE NC
PIN NUMBER: 9672712573, 9672512885, 967240371
9672410864, 9671485404, 967240583

PROPERTY SIZE: PH1: 82.78 AC - TOTAL: 245.86 AC

ZONING REVIEW: HENDERSON COUNTY

EROSION CONTROL REVIEW: HENDERSON COUNTY

STORMWATER REVIEW: HENDERSON COUNTY

ZONING CLASSIFICATION: R3

PROPOSED NUMBER OF UNITS: PH1: 22 - TOTAL: 60

PROPOSED DENSITY: PH1: 0.26 LOTS/AC - TOTAL: 0.244 LOTS / AC

PROPOSED LINEAR FEET OF ROAD: PHASE 1: 3,654 LF

TOTAL ON PROPERTY: 9,856 LF

OFF PROPERTY EASEMENT: 2,934 LF

LOTS 1-51 ARE LOCATED IN A FARMLAND PRESERVATION DISTRICT, LOTS

52-60 ARE WITHIN 1/2 MILE OF A THE FARMLAND PRESERVATION

DISTRICT

WATER AND SEWER WILL BE PROVIDED BY INDIVIDUAL WELLS AND SEPTIC

SYSTEMS

PUBLIC WATER AND SEWER ARE APPROXIMATELY 3.0 MILES FROM THE SITE

DRY HYDRANT IS LOCATED APPROXIMATELY 0.90 ROAD MILES FROM THE

ENTRANCE TO THE SITE

PROPERTY OWNER: MULTIPLE OWNERS -
SEE SHEET C-0
FOR CONTACT INFORMATION

DEVELOPER: RIPPLE FALLS LLC

CONTACT: ANDY BAKER

ADDRESS: 69 CLARK GAP ROAD

FLETCHER NC

EMAIL: ANDY@TFMCAROLINA.COM

PHONE: (616) 402-0367

ENGINEER: BROOKS ENGINEERING


CONTACT: WYATT EDSLE PE

ADDRESS: 15 ARLINGTON ST

ASHEVILLE, NC 28801

EMAIL: WEDSEL@BROOKSEA.COM

PHONE: 828-232-4700



SCALE: 1" = 50

SHEET C-4.5

6

SHEET C-4.7

HELLE

Sq. Feet

56 Acres

EXIST. BOUNDARY

EXIST. ADJOINER

EXIST. STREAM

EXIST. STREAM BUFFER

EXIST. WETLAND

EXIST. FEMA NON-ENCROACHMENT

FEMA FLOOD HAZARD AREA (1%)

FEMA FLOOD HAZARD AREA (0.2%)

EXIST. RIGHT OF WAY

EXIST. BUILDING SETBACK

EXIST. BUILDING

EXISTING SIDEWALK

EXISTING PAVEMENT

EXIST. CURB

NEW PROPERTY LINES

NEW RIGHT OF WAY

NEW EASEMENT

BUILDING SETBACK LINE

NEW LANDSCAPE BUFFER

NEW COMMON OPEN SPACE

NEW BUILDING

NEW PAVEMENT

NEW HD PAVEMENT

NEW CONCRETE SIDEWALK

NEW GRAVEL

NEW CURB & GUTTER

NEW WALL (BY OTHERS)

PROPOSED CENTER LINE (TYP)

C201

L247

C130

L210

L211

C164

L246

C200

L212

L213

C163

C165

C166

C199

C198

L215

L216

C167

C168

C169

C170

C171

C172

C173

C174

C175

C176

C177

C178

C179

C180

C181

C182

C183

C184

C185

C186

C187

C188

C189

C190

C191

C192

C193

C194

C195

C196

C197

C198

C199

C200

C201

C202

C203

C204

C205

C206

C207

C208

C209

C210

C211

C212

C213

C214

C215

C216

C217

C218

C219

C220

C221

C222

C223

C224

C225

C226

C227

C228

C229



C230

C231


C232

SEE CONTINUATION ON SHEET C-4.8


SEE CONTINUATION ON THIS SHEET




SEE CONTINUATION ON THIS SHEET




HORIZONTAL SCALE: 1"=50'




SEE CONTINUATION ON SHEET C-4.10



ANSWER




VERTICAL SCALE: 1"=20'




SEE CONTINUATION ON THIS SHEET

SEE CONTINUATION ON THIS SHEET



SEE CONTINUATION ON THIS SHEET



HORIZONTAL SCALE: 1"=50'

SEE CONTINUATION ON THIS SHEET

SEE CONTINUATION ON THIS SHEET

PRELIMINARY - NOT FOR CONSTRUCTION

| No. | REVISIONS/SUBMISSIONS | Date |
|-----|-----------------------|------------|
| 1 | HENDERSON COUNTY TRC | 11-02-2021 |

Revision/Submission number with a triangle indicates changes made on this sheet

SEE CONTINUATION ON SHEET C-4.13

14+34.67
V: 2600.52







| | No. | R |
|--|-----|----|
| | 1 | HE |

CAR
ESSIONAL
H. Edsel
SEAL
5408
ENGINEER
TENTLEY
NEERI/
NORTH
CROLINA
C-312


PRELIMINARY - NOT FOR


CONSTRUCTION
Revision/Submission number

ROAD PROFILES

**SEE CONTINUATION ON SHEET C-4.12****SEE CONTINUATION ON THIS SHEET**

| | | | |
|--|--|---|--|
| Project No: 543521 | RICH MOUNTAIN SUBDIVISION PHASE 1 RESIDENTIAL SUBDIVISION HENDERSON COUNTY NORTH CAROLINA | BROOKS ENGINEERING ASSOCIATES Planning • Engineering • Surveying • Environmental Services • | Reviewed: WBE Scale: AS NOTED Date: 2021-11-02 |
| C-4.13 | ROAD PROFILES | Designed: WBE Drawn: WBE Checked: WBE Date: 2021-11-02 | No. 1 REVISIONS/SUBMISSIONS HENDERSON COUNTY TRC 11-02-2021 |
| | | PRELIMINARY - NOT FOR CONSTRUCTION | |
| <p>Revision Submission number within a triangle indicates changes made on this sheet</p> <p>File Location: L:\2021\Projects\543521\Rapile Falls Rich Mtn Due Diligence\Drawings\CV-Base-543521.dwg</p> | | | |



**DEVELOPMENT DATA**

PROPERTY ADDRESS: LOCUST GROVE ROAD HENDERSONVILLE NC
PIN NUMBER: 9672712573, 9672512885, 967240371
9672410864, 9671485404, 967240583
PROPERTY SIZE: PH1: 82.78 AC. TOTAL: 245.86 AC
ZONING REVIEW: HENDERSON COUNTY
EROSION CONTROL REVIEW: HENDERSON COUNTY
STORMWATER REVIEW: HENDERSON COUNTY
ZONING CLASSIFICATION: R3
PROPOSED NUMBER OF UNITS: PH1: 22 -TOTAL: 60
PROPOSED DENSITY: PH1: 0.26 LOTS/AC - TOTAL: 0.244 LOTS / AC
PROPOSED LINEAR FEET OF ROAD: PHASE 1: 3,654 LF
TOTAL ON PROPERTY: 9,856 LF
OFF-PROPERTY EASEMENT: 2,934 LF
LOTS 1-51 ARE LOCATED IN A FARMLAND PRESERVATION DISTRICT, LOTS 52-60 ARE WITHIN 1/2 MILE OF THE FARMLAND PRESERVATION DISTRICT
WATER AND SEWER WILL BE PROVIDED BY INDIVIDUAL WELLS AND SEPTIC SYSTEMS
PUBLIC WATER AND SEWER ARE APPROXIMATELY 3.0 MILES FROM THE SITE
DRY HYDRANT IS LOCATED APPROXIMATELY 0.90 ROAD MILES FROM THE ENTRANCE TO THE SITE
PROPERTY OWNER: MULTIPLE OWNERS - SEE SHEET C-0 FOR CONTACT INFORMATION
DEVELOPER: RIPPLE FALLS LLC
CONTACT: ANDY BAKER
ADDRESS: 69 CLARK GAP ROAD
FLETCHER NC
EMAIL: ANDY@TFMCAROLINA.COM
PHONE: (616) 402-0367
ENGINEER: BROOKS ENGINEERING
CONTACT: WYATT EDSSEL PE
ADDRESS: 15 ARLINGTON ST
ASHEVILLE, NC 28801
EMAIL: WEDSEL@BROOKSEA.COM
PHONE: 828-232-4700

STORM AND EROSION NOTES

PROPERTY SIZE: PH1: 82.78 AC - TOTAL: 245.86 AC.
PROPERTY STEEPER THAN 60%: 16.78 AC (6.82%)
PROJECT DENSITY: PH1: 0.26 LOTS/AC - TOTAL: 0.244 LOTS/AC.
IMPERVIOUS SUMMARY:
ROADS: PH1: 3.27 AC - TOTAL: 6.14 AC.
HOUSES & DRIVES (15,000 SF / LOT): 7.58 AC - 20.66 AC.
TOTAL: 10.85 AC. (13.11%) - 26.80 AC. (10.90%)


EROSION CONTROL NOTES:

1. SEE SHEET C-5.10 FOR STABILIZATION TIME FRAMES.
2. EROSION CONTROL MEASURES SHALL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE AND AN AMENDED PLAN BE SUBMITTED AND APPROVED SHOWING MODIFIED EROSION CONTROL DEVICES.


STORMWATER NOTES:


1. ALL STREAMS SHALL HAVE A 30' SETBACK FOR NEW BUILT-UPON AREAS.
2. ALL PIPE SHALL BE DOUBLE-WALL HDPE WITH PROPER STONE BEDDING AND SHALL HAVE A MINIMUM COVER OF 30'.
3. ALL FILL SLOPES SHALL BE COMPACTED FULL DEPTH TO NOT LESS THAN 95 PERCENT MAXIMUM DENSITY (STANDARD PROCTOR), SHALL BE PLACED ON A SURFACE CLEAR OF GROWTH AND DEBRIS AND BE PROPERLY BENCHED AND DRAINED.
4. ALL SLOPES GREATER THAN 3:1 AND TALLER THAN 10 FEET SHALL BE SEDED AND COVERED WITH MATTING AS SHOWN IN THE PLANS.
5. AN APPROVED GRADING PERMIT IS REQUIRED FOR ANY BORROW OR WASTE SITE PRIOR TO INITIATION OF ANY LAND DISTURBING ACTIVITY.

*ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF DETAILS, SPECIFICATIONS, AND OTHER DEVELOPMENT ORDINANCES OF HENDERSON CO.



SCALE: 1" = 300





GRADING AND STORMWATER LEGEND

- EXIST. BOUNDARY
- EXIST. ADJOINER
- EXIST. STREAM
- EXIST. STREAM BUFFER
- EXIST. RIGHT OF WAY
- EXIST. EASEMENT
- EXIST. BUILDING SETBACK
- EXISTING BUILDING
- EXISTING SIDEWALK
- EXISTING PAVEMENT
- EXIST. CURB
- EXIST. MANHOLE
- EXIST. SANITARY SEWER
- EXIST. SEWER CLEAN OUT
- EXIST. WATER LINE
- EXIST. WATER METER
- EXIST. FIRE HYDRANT
- EXIST. WATER VALVE
- EXIST. OVERHEAD UTILITIES
- EXIST. UNDERGRND UTILITIES
- EXIST. STORM DRAIN
- EXIST. CURB INLET
- EXIST. JUNCTION BOX
- EXIST. DROP INLET
- EXIST. TELE. MANHOLE
- EXIST. DROP INLET
- EXIST. TRANSFORMER
- EXIST. LIGHT POLE
- EXIST. MINOR CONTOUR
- EXIST. MAJOR CONTOUR
- NEW BUILDING
- NEW PAVEMENT
- NEW HEADWALL
- NEW FLARED END SECTION
- NEW STORM PIPE
- RIP RAP LINED DITCH
- NEW MINOR CONTOUR
- NEW MAJOR CONTOUR
- NEW SPOT GRADE
- NEW PROPERTY LINES
- NEW RIGHT OF WAY
- LIMITS OF DISTURBANCE
- NEW WALL (BY OTHERS)

PROPERTY ADDRESS: LOCUST GROVE ROAD HENDERSONVILLE NC
PIN NUMBER: 9672712573, 9672512885, 967240371 9672410864, 9671485404, 967240583
PROPERTY SIZE: PH1: 82.78 AC - TOTAL: 245.86 AC
ZONING REVIEW: HENDERSON COUNTY
EROSION CONTROL REVIEW: HENDERSON COUNTY
STORMWATER REVIEW: HENDERSON COUNTY
ZONING CLASSIFICATION: R3
PROPOSED NUMBER OF UNITS: PH1: 22 - TOTAL: 60
PROPOSED DENSITY: PH1: 0.26 LOTS/AC - TOTAL: 0.244 LOTS / AC
PROPOSED LINEAR FEET OF ROAD: PHASE 1: 3,654 LF
TOTAL ON PROPERTY: 9,856 LF
OFF-PROPERTY EASEMENT: 2,934 LF
LOTS 1-51 ARE LOCATED IN A FARMLAND PRESERVATION DISTRICT, LOTS 52-60 ARE WITHIN 1/2 MILE OF A THE FARMLAND PRESERVATION DISTRICT
WATER AND SEWER WILL BE PROVIDED BY INDIVIDUAL WELLS AND SEPTIC SYSTEMS
PUBLIC WATER AND SEWER ARE APPROXIMATELY 3.0 MILES FROM THE SITE
DRY HYDRANT IS LOCATED APPROXIMATELY 0.90 ROAD MILES FROM THE ENTRANCE TO THE SITE
PROPERTY OWNER: MULTIPLE OWNERS - SEE SHEET C-6 FOR CONTACT INFORMATION
DEVELOPER: RIPPLE FALLS LLC
CONTACT: ANDY BAKER
ADDRESS: 69 CLARK GAP ROAD FLETCHER NC
EMAIL: ANDY@TFMCAROLINA.COM
PHONE: (616) 402-0367
ENGINEER: BROOKS ENGINEERING
CONTACT: WYATT EDSSEL PE
ADDRESS: 15 ARLINGTON ST ASHEVILLE, NC 28801
EMAIL: WEDSEL@BROOKSEA.COM
PHONE: 828-232-4700

STORM AND EROSION NOTES

PROPERTY SIZE: PH1: 82.78 AC. - TOTAL: 245.86 AC.
PROPERTY STEEPER THAN 60%: 16.76 AC (6.82%)
PROJECT DENSITY: PH1: 0.26 LOTS/AC. - TOTAL 0.244 LOTS/AC.
IMPERVIOUS SUMMARY:
ROADS: PH1: 3.27 AC. - TOTAL: 6.14 AC.
HOUSES & DRIVES (15,000 SF / LOT): 7.58 AC. - 20.66 AC.
TOTAL: 10.85 AC. (13.11%) - 26.80 AC. (10.90%)

EROSION CONTROL NOTES:

- SEE SHEET C-5.10 FOR STABILIZATION TIME FRAMES
- EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE AND AN AMENDED PLAN BE SUBMITTED AND APPROVED SHOWING MODIFIED EROSION CONTROL DEVICES.

STORMWATER NOTES:

- ALL STREAMS SHALL HAVE A 30' SETBACK FOR NEW RIJI-TJUPON AREAS
- ALL PIPE SHALL BE DOUBLE-WALL HDPE WITH PROPER STONE BEDDING AND SHALL HAVE A MINIMUM COVER OF 30'
- ALL FILL SLOPES SHALL BE COMPACTED FULL DEPTH TO NOT LESS THAN 95 PERCENT MAXIMUM DENSITY (STANDARD PROCTOR) SHALL BE PLACED ON A SURFACE CLEAR OF GROWTH AND DEBRIS AND BE PROPERLY BENCHED AND DRAINED.
- ALL SLOPES GREATER THAN 3:1 AND TALLER THAN 10 FEET SHALL BE SEDED AND COVERED WITH MATTING AS SHOWN IN THE PLANS.
- AN APPROVED GRADING PERMIT IS REQUIRED FOR ANY BORROW OR WASTE SITE PRIOR TO INITIATION OF ANY LAND DISTURBING ACTIVITY.

*ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF DETAILS, SPECIFICATIONS, AND OTHER DEVELOPMENT ORDINANCES OF HENDERSON CO.

SHEET C-5.3

SWALE CHART

| Swale Name | Swale Type | Up Invert | Down Invert | Side Slope - Z | b(tn) | Length | Slope | DRAINAGE | | | | | structure | Upstream q | Total q | RESULTS | | | | | |
|------------|------------|-----------|-------------|----------------|--------|---------|-------|-------------|-------------|---------|-------|----------------|-----------|------------|---------|----------|-----------|-----------|------------|---------|---------------------------|
| | | | | | | | | Da to Inlet | Da to Inlet | C Value | TOC | I _s | | | | q swale | nf | structure | Upstream q | Total q | Flow Depth |
| SW4 | GRASS | 2690.0' | 2674.0' | 3.0 | 0.0 ft | 485 ft | 7.2% | 245,652 sf | 5.6 ac | 0.36 | 5 min | 8.34 | 16.93 cfs | 0.025 | none | 0.00 cfs | 16.93 cfs | 13.6 in | 4.4 fps | 0.67 | Straww Net (Temporary) |
| SW5 | GRASS | 2690.0' | 2680.0' | 3.0 | 0.0 ft | 250 ft | 4.0% | 5,697 sf | 0.1 ac | 0.63 | 5 min | 8.34 | 0.69 cfs | 0.025 | none | 0.00 cfs | 0.69 cfs | 3.8 in | 3.4 fps | 0.67 | Straww Net (Temporary) |
| SW6 | GRASS | 2690.0' | 2680.0' | 3.0 | 0.0 ft | 350 ft | 2.9% | 56,793 sf | 1.3 ac | 0.39 | 5 min | 8.34 | 4.24 cfs | 0.025 | none | 0.00 cfs | 4.24 cfs | 6.8 in | 4.4 fps | 1.02 | Straww Net (Temporary) |
| SW7 | GRASS | 2686.0' | 2680.0' | 3.0 | 0.0 ft | 275 ft | 2.2% | 9,057 sf | 0.2 ac | 0.56 | 5 min | 8.34 | 0.86 cfs | 0.025 | none | 0.00 cfs | 0.86 cfs | 4.0 in | 2.6 fps | 0.45 | Straww Net (Temporary) |
| SW8 | RIP-RAP | 2688.0' | 2710.0' | 3.0 | 0.0 ft | 1170 ft | 15.2% | 99,599 sf | 2.1 ac | 0.43 | 5 min | 8.34 | 7.46 cfs | 0.035 | none | 0.00 cfs | 7.46 cfs | 7.7 in | 7.1 fps | 5.60 | 18in d50 Rip/Rap |
| SW9 | GRASS | 2762.0' | 2740.0' | 3.0 | 0.0 ft | 150 ft | 14.7% | 3,173 sf | 0.1 ac | 0.62 | 5 min | 8.34 | 0.38 cfs | 0.025 | none | 0.00 cfs | 0.38 cfs | 2.0 in | 4.3 fps | 1.56 | Synthetic Net (Temporary) |

PIPE CHART

| Pipe Name | Road Elevation | Up Invert | Down Invert | Pipe Size | Material | Length | Slope | DRAINAGE | | | | | structure | Upstream flow | Total q | RESULTS | | | | | | | |
|-----------|----------------|-----------|-------------|-----------|----------|--------|-------|--------------|-------------|---------|-------|----------------|-----------|---------------|---------|----------|-----------|-----------|------------|---------|------------|----------|----------------|
| | | | | | | | | Da to Inlet | Da to Inlet | C Value | TOC | I _s | | | | q inlet | nf | structure | Upstream q | Total q | Flow Depth | Velocity | d50 Stone Size |
| P2 | 2674.0' | 2670.0' | 2658.0' | 24 0 in | HDPE | 55 ft | 21.3% | 245,652 sf | 5.6 ac | 0.36 | 5 min | 8.34 | 16.93 cfs | 0.011 | none | 0.00 cfs | 16.93 cfs | 6.2 in | 26.6 lbs | 6 in | 9 in | 15 ft | 21 ft |
| P3 | 2683.0' | 2678.0' | 2668.0' | 36 0 in | HDPE | 36 ft | 27.3% | 507,897 sf | 11.7 ac | 0.35 | 5 min | 8.34 | 34.03 cfs | 0.011 | SW6 | 4.24 cfs | 38.28 cfs | 7.7 in | 34.6 lbs | 12 in | 18 in | 20 ft | 29 ft |
| P4 | 2689.0' | 2683.0' | 2682.0' | 48 0 in | HDPE | 36 ft | 2.8% | 1,298,088 sf | 29.8 ac | 0.36 | 5 min | 8.34 | 89.47 cfs | 0.011 | none | 0.00 cfs | 89.47 cfs | 18.7 in | 19.8 lbs | 18 in | 31 in | 25 ft | 37 ft |

PIRE CALCULATIONS

PROPOSED RIPRAP LINED DITCH (TYP) (SEE SWALE CHART ON THIS SHEET)

PROPOSED 2FT CONTOURS (TYP)

PROPOSED SILT FENCE OUTLET (TYP) (SEE SHEET C-5.8)

PROPOSED SLOPE MATTING (TYP) (SEE SHEET C-5.9)

PROPOSED HEAD WALL (TYP)

PROPOSED SILT FENCE (TYP) (SEE SHEET C-5.8)

PROPOSED STORM PIPE (TYP) (SEE PIPE CHART ON THIS SHEET)

PROPOSED LIMITS OF DISTURBANCE (TYP)

PROPOSED 20FT PAVED ROAD (TYP) (SEE SHEET C-4.14)

PROPOSED 45FT RIGHT OF WAY (TYP)

EXISTING 2FT CONTOURS (TYP)

PROPOSED CHECK DAM (TYP) (SEE SHEET C-5.8)

PROPOSED RIPRAP OUTLET PROTECTION (TYP) (SEE SHEET C-5.8)

PROPOSED ROCK INLET PROTECTION (TYP) (SEE SHEET C-5.8)

SHEET C-5.1

REVISIONS/SUBMISSIONS

| | |
|-----|----------------------|
| No. | HENDERSON COUNTY TRC |
| 1 | |

REVISIONS/SUBMISSIONS

| | |
|------|------------|
| Date | 11-02-2021 |
|------|------------|

SEAL

NO. 45408

PRELIMINARY - NOT FOR CONSTRUCTION

BROOKS ENGINEERING ASSOCIATES

Planning • Engineering • Surveying • Environmental Services.

Project No: 543521

Drawing Title: EC, GRADING, & STORMWATER PLAN 2

RESIDENTIAL SUBDIVISION

HENDERSON COUNTY

NORTH CAROLINA

15 Arlington Street

Asheville, N.C. 28801

Phone: 1-828-23-4700

Fax: 1-828-232-1331

www.brooksca.com

Reviewed: WB
Drawn: WB
Scale: AS NOTED
Created: WB
Date: 2021-11-02

GRADING AND STORMWATER LEGEND

| | | |
|-------|---------------------------|------------|
| | EXIST. BOUNDARY | PROPERTY |
| | EXIST. ADJOINER | PIN NUMBER |
| | EXIST. STREAM | PROPERTY |
| | EXIST. STREAM BUFFER | ZONING |
| | EXIST. RIGHT OF WAY | EROSION |
| | EXIST. EASEMENT | STORMWATER |
| | EXIST. BUILDING SETBACK | ZONING |
| | EXISTING BUILDING | PROPOSED |
| | EXISTING SIDEWALK | PROPOSED |
| | EXISTING PAVEMENT | PROPOSED |
| | EXIST. CURB | LOTS 1-51 |
| | EXIST. MANHOLE | 52-60 |
| | EXIST. MANHOLE | DIST. |
| | EXIST. SANITARY SEWER | WATER A |
| | EXIST. SEWER CLEAN OUT | SYS |
| | EXIST. WATER LINE | PUBLIC W |
| | EXIST. WATER METER | DRY HYD |
| | EXIST. FIRE HYDRANT | ENT. |
| | EXIST. WATER VALVE | PROPERTY |
| | EXIST. OVERHEAD UTILITIES | DEVELOP |
| | EXIST. POWER POLE | COMP |
| | EXIST. UNDRGRND UTILITIES | ADD |
| | EXIST. STORM DRAIN | EMAIL |
| | EXIST. CURB INLET | PHONE |
| | EXIST. JUNCTION BOX | ENGINEER |
| | EXIST. DROP INLET | COMP |
| | EXIST. TELE MANHOLE | ADD |
| | EXIST. DROP INLET | EMAIL |
| | EXIST. TRANFORMER | PHONE |
| | EXIST. LIGHT POLE | |
| | EXIST. MINOR CONTOUR | |
| | EXIST. MAJOR CONTOUR | |
| | NEW BUILDING | |
| | NEW PAVEMENT | |
| | NEW HEADWALL | |
| | NEW FLARED END SECTION | |
| | NEW STORM PIPE | |
| | RIP RAP LINED DITCH | |
| ELEV | NEW MINOR CONTOUR | |
| | NEW MAJOR CONTOUR | |
| +17.0 | NEW SPOT GRADE | |
| | NEW PROPERTY LINES | |
| | NEW RIGHT OF WAY | |
| | LIMITS OF DISTURBANCE | |
| | NEW WALL (BY OTHERS) | |

STORM AND EROSION NOTES

PROPERTY SIZE: PH1: 82.78 AC. - TOTAL: 245.86 AC.

PROPERTY STEEPER THAN 60%: 16.76 AC (6.82%)

PROJECT DENSITY: PH1: 0.26 LOTS/AC. - TOTAL 0.244 LOTS/AC.

IMPERVIOUS SUMMARY:

ROADS: PH1: 3.27 AC. - TOTAL: 6.14 AC.

HOUSES & DRIVES (15,000 SF / LOT): 7.58 AC. - 20.66 AC.

TOTAL: 10.85 AC. (13.11%) - 26.80 AC. (10.90%)


EROSION CONTROL NOTES:

- SEE SHEET C-5.10 FOR STABILIZATION TIME FRAMES.
- EROSION CONTROL MEASURES WILL BE MAINTAINED AT ALL TIMES. IF FULL IMPLEMENTATION OF THE APPROVED PLAN DOES NOT PROVIDE FOR EFFECTIVE EROSION CONTROL, ADDITIONAL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IMPLEMENTED TO CONTROL OR TREAT THE SEDIMENT SOURCE AND AN AMENDED PLAN BE SUBMITTED AND APPROVED SHOWING MODIFIED EROSION CONTROL DEVICES.


STORMWATER NOTES:

- ALL STREAMS SHALL HAVE A 30' SETBACK FOR NEW BUILT-UPON AREAS.
- ALL PIPE SHALL BE DOUBLE-WALL HDPE WITH PROPER STONE BEDDING AND SHALL HAVE A MINIMUM COVER OF 30".
- ALL FILL SLOPES SHALL BE COMPACTED FULL DEPTH TO NOT LESS THAN 95 PERCENT MAXIMUM DENSITY (STANDARD PROCTOR), SHALL BE PLACED ON A SURFACE CLEAR OF GROWTH AND DEBRIS AND BE PROPERLY BENCHED AND DRAINED.
- ALL SLOPES GREATER THAN 3:1 AND TALLER THAN 10 FEET SHALL BE SEADED AND COVERED WITH MATTING AS SHOWN IN THE PLANS.
- AN APPROVED GRADING PERMIT IS REQUIRED FOR ANY BORROW OR WASTE SITE PRIOR TO INITIATION OF ANY LAND DISTURBING ACTIVITY.

*ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF DETAILS, SPECIFICATIONS, AND OTHER DEVELOPMENT ORDINANCES OF HENDERSON CO.



SCALE: 1 = 5



SHEET C-5.2

| PIPE CHART | | | | | | | | PIPE CALCULATIONS | | | | | | | | | | | | | | | | |
|------------|----------------|-----------|-------------|-----------|---------------|--------|-------|-------------------|-------------|---------|--------|-----------------|-----------|-------|---------------|------------|-------------|------------|----------|----------------|-------------------------|------------|-----------|--|
| Pipe Name | Road Elevation | Up Invert | Down Invert | Pipe Size | Pipe Material | Length | Slope | DRAINAGE | | | | | | nf | UPSTREAM FLOW | | DESIGN FLOW | | RESULTS | | OUTLET PROTECTION CALCS | | | |
| | | | | | | | | Da to Inlet | Da to Inlet | C Value | TOC | I ₂₅ | q inlet | | structure | Upstream q | Total q | Flow Depth | Velocity | d50 Stone Size | Apron Thickness | Pad Length | Pad Width | |
| P5 | 2888.0' | 2883.0' | 2868.0' | 36.0 in | HDPE | 67 ft | 22.4% | 662,845 sf | 15.2 ac | 0.40 | 15 min | 5.61 | 34.15 cfs | 0.011 | none | 0.00 cfs | 34.15 cfs | 7.7 in | 31.0 fps | 12 in | 18 in | 20 ft | 29 ft | |
| P6 | 2899.0' | 2894.5' | 2894.0' | 30.0 in | HDPE | 40 ft | 1.3% | 296,955 sf | 6.8 ac | 0.41 | 5 min | 8.34 | 23.31 cfs | 0.011 | SW12 | 1.59 cfs | 24.90 cfs | 14.2 in | 10.8 fps | 12 in | 18 in | 15 ft | 23 ft | |
| P7 | 2902.0' | 2896.5' | 2892.0' | 42.0 in | HDPE | 36 ft | 12.5% | 701,008 sf | 16.1 ac | 0.44 | 5 min | 8.34 | 59.05 cfs | 0.011 | SW13 | 6.04 cfs | 65.09 cfs | 11.5 in | 30.5 fps | 12 in | 18 in | 25 ft | 36 ft | |

| SWALE CHART | | | | | | | | SWALE CALCULATIONS | | | | | | | | | | | | | | |
|-------------|------------|-----------|-------------|----------------|-----------------|---------|-------|--------------------|-------------|---------|-------|-----------------|-----------|-------|---------------|------------|-------------|------------|----------|--------------|---------------------------|--|
| Swale Name | Swale Type | Up Invert | Down Invert | Side Slope - Z | btm width b(ft) | Length | Slope | DRAINAGE | | | | | | nf | UPSTREAM FLOW | | DESIGN FLOW | | RESULTS | | | |
| | | | | | | | | Da to Inlet | Da to Inlet | C Value | TOC | I ₂₅ | q swale | | structure | Upstream q | Total q | Flow Depth | Velocity | Sheer Stress | Reinforcement | |
| SW8 | RIP-RAP | 2888.0' | 2710.0' | 3.0 | 0.0 ft | 1170 ft | 15.2% | 90,599 sf | 2.1 ac | 0.43 | 5 min | 8.34 | 7.46 cfs | 0.035 | none | 0.00 cfs | 7.46 cfs | 7.1 in | 7.1 fps | 5.60 | 18in d50 Rip Rap | |
| SW9 | GRASS | 2762.0' | 2740.0' | 3.0 | 0.0 ft | 150 ft | 14.7% | 3,173 sf | 0.1 ac | 0.62 | 5 min | 8.34 | 0.38 cfs | 0.025 | none | 0.00 cfs | 0.38 cfs | 2.0 in | 4.3 fps | 1.56 | Synthetic Net (Temporary) | |
| SW10 | RIP-RAP | 2884.0' | 2790.0' | 3.0 | 0.0 ft | 610 ft | 15.4% | 40,060 sf | 0.9 ac | 0.44 | 5 min | 8.34 | 3.37 cfs | 0.035 | none | 0.00 cfs | 3.37 cfs | 5.2 in | 6.1 fps | 4.13 | 12in d50 Rip Rap | |
| SW11 | RIP-RAP | 2900.0' | 2890.0' | 3.0 | 0.0 ft | 400 ft | 2.5% | 662,845 sf | 15.2 ac | 0.40 | 5 min | 8.34 | 50.76 cfs | 0.035 | none | 0.00 cfs | 50.76 cfs | 20.4 in | 5.9 fps | 2.65 | 6in d50 Rip Rap | |

C-5

| | |
|-------------------------------|--|
| Drawing Title: | |
| HENDERSON COUNTY | |
| E&C GRADING & STORMWATER PLAN | |

H MOUNTAIN SUBDIVISION PHASE 1


RESIDENTIAL SUBDIVISION


ENGINEERING ASSOCIATES


Planning • Engineering • Surveying


Environmental Services

| | | | |
|---|-----|---------------------------|------------|
| WBE | WBE | Scale: AS NOTED | 11-02-2021 |
| Drawn: | WBE | Checked: | WBE |
| | | Date: | 2021-11-02 |
| <p>HENDERSON COUNTY TRC</p> <p>PRELIMINARY - NOT FOR CONSTRUCTION</p>   | | | |
| <p>15 Arlington Street Asheville, N.C. 28801 Phone: 1-828-232-4700 Fax: 1-828-232-1331 www.brooksea.com</p> | | | |












Figure 6.06a Gravel entrance/exit keeps sediment from leaving the construction site (modified from Va SWCC).

Washing—If conditions at the site are such that most of the mud and sediment are not removed by vehicles traveling over the gravel, the tires should be washed. Washing should be done on an area stabilized with crushed stone that drains into a sediment trap or other suitable disposal area. A wash rack may also be used to make washing more convenient and effective.

- Construction Specifications**
1. Clear the entrance and exit area of all vegetation, roots, and other objectionable material and properly grade it.
 2. Place the gravel to the specific grade and dimensions shown on the plans, and smooth it.
 3. Provide drainage to carry water to a sediment trap or other suitable outlet.
 4. Use geotextile fabrics because they improve stability of the foundation in locations subject to seepage or high water table.

- Maintenance** Maintain the gravel pad in a condition to prevent mud or sediment from leaving the construction site. This may require periodic topdressing with 2-inch stone. After each rainfall, inspect any structure used to trap sediment and clean it as necessary. Immediately remove all objectionable materials spilled, washed, or tracked onto public roadways.

A CONSTRUCTION ENTRANCE/EXIT - NCDEQ 6.06

SCALE= NTS

- Construction Specifications**
1. Place stone to the lines and dimensions shown in the plan on a filter fabric foundation.
 2. Keep the center stone section at least 9 inches below natural ground level where the dam abuts the channel banks.
 3. Extend stone at least 1.5 feet beyond the ditch bank (Figure 6.83b) to keep water from cutting around the ends of the check dam.
 4. Set spacing between dams to assure that the elevation at the top of the lower dam is the same as the toe elevation of the upper dam.
 5. Protect the channel after the lowest check dam from heavy flow that could cause erosion.
 6. Make sure that the channel reach above the most upstream dam is stable.
 7. Ensure that other areas of the channel, such as culvert entrances below the check dams, are not subject to damage or blockage from displaced stones.




Figure 6.83a Space check dams in a channel so that the crest of downstream dam is at elevation of the toe of upstream dam.

D TEMPORARY CHECK DAM SPACING SPECIFICATION

SCALE= NTS

Construction MATERIALS
Specifications

1. Use a synthetic filter fabric of at least 95% by weight of polyethylene or polyester, which is certified by the manufacturer or supplier as conforming to the requirements in ASTM D 6461, which is shown in part in Table 6.62b.

Synthetic filter fabric should contain ultraviolet ray inhibitors and stabilizers to provide a minimum of 6 years of expected usable construction life at a minimum temperature of 100°F.

2. Ensure that posts for sediment fences are 1.25 lb/inch ft minimum steel with a minimum length of 5' feet. Make sure that steel posts have projections to facilitate fastening the fabric.

3. For reinforcement of standard strength filter fabric, use wire fence with a minimum 14 gauge and a maximum mesh spacing of 6 inches.

Table 6.62b Specifications For Sediment Fence Fabric

| Temporary Silt Fence Material Property Requirements | | Type of Value | | | |
|---|-------------|----------------------|----------------------------|----------------------------|-----------------------|
| Test Material | Units | Supported Silt Fence | Un-Supported Silt Fence | | |
| Grab Strength | ASTM D 4632 | N (lbs) | 400 | 550 | MARV |
| Machine Direction | | | (90) | (90) | |
| X-Machine Direction | | | 400 | 450 | MARV |
| Permeability ^a | ASTM D 4491 | sec-1 | 0.05 | 0.05 | MARV |
| Apparent Opening Size ^b | ASTM D 4751 | mm | 0.80 | 0.60 | Max. ARV ^c |
| Ultraviolet Stability | ASTM D 4355 | Retained Strength | 70% after 500h of exposure | 70% after 500h of exposure | Typical |

^a Silt fence support shall consist of 14 gauge steel wire with a mesh spacing of 150 mm (6 inches), or prefabricated polymer mesh of equivalent strength.^b These default values are based on empirical evidence with a variety of sediment. For environmentally sensitive areas, a review of previous experience and/or site or regionally specific geotextile tests in accordance with Test Method D 5141 should be performed by the agency to confirm suitability of these requirements.^c As measured in accordance with Test Method D 4632.

GROUND STABILIZATION AND MATERIALS HANDLING PRACTICES FOR COMPLIANCE WITH THE NCG01 CONSTRUCTION GENERAL PERMIT

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCG01 Construction General Permit (Sections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

SECTION E: GROUND STABILIZATION

Required Ground Stabilization Timeframes

| Site Area Description | Stabilize within this many calendar days after ceasing land disturbance | Timeframe variations |
|--|---|---|
| (a) Perimeter dikes, swales, ditches, and perimeter slopes | 7 | None |
| (b) High Quality Water (HQW) Zones | 7 | None |
| (c) Slopes steeper than 3:1 | 7 | If slopes are 10' or less in length and are not steeper than 2:1, 14 days are allowed |
| (d) Slopes 3:1 to 4:1 | 14 | -7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed |
| (e) Areas with slopes flatter than 4:1 | 14 | -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope |

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

GROUND STABILIZATION SPECIFICATION

Stabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below:

| Temporary Stabilization | Permanent Stabilization |
|---|--|
| ◦ Temporary grass seed covered with straw or other mulches and tackifiers | ◦ Permanent grass seed covered with straw or other mulches and tackifiers |
| ◦ Hydroseeding | ◦ Geotextile fabrics such as permanent soil reinforcement matting |
| ◦ Rolled erosion control products with or without temporary grass seed | ◦ Hydroseeding |
| ◦ Appropriately applied straw or other mulch | ◦ Shrubs or other permanent plantings covered with mulch |
| ◦ Plastic sheeting | ◦ Uniform and evenly distributed ground cover sufficient to restrain erosion |
| | ◦ Structural methods such as concrete, asphalt or retaining walls |
| | ◦ Rolled erosion control products with grass seed |

POLYACRYLAMIDES (PAMS) AND FLOCCULANTS

- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NC DWR List of Approved PAMS/Flocculants .
- Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
- Apply flocculants at the concentrations specified in the NC DWR List of Approved PAMS/Flocculants and in accordance with the manufacturer's instructions.
- Provide ponding area for containment of treated Stormwater before discharging offsite.
- Store flocculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

EQUIPMENT AND VEHICLE MAINTENANCE

- Maintain vehicles and equipment to prevent discharge of fluids.
- Provide drip pans under any stored equipment.
- Identify leaks and repair as soon as feasible, or remove leaking equipment from the project.
- Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when possible).
- Remove leaking vehicles and construction equipment from service until the problem has been corrected.
- Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- Never bury or burn waste. Place litter and debris in approved waste containers.
- Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes.
- Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
- Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers.
- Anchor all lightweight items in waste containers during times of high winds.
- Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow.
- Dispose waste off-site at an approved disposal facility.
- On business days, clean up and dispose of waste in designated waste containers.

PAINT AND OTHER LIQUID WASTE


- Do not dump paint and other liquid waste into storm drains, streams or wetlands.
- Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Contain liquid wastes in a controlled area.
- Containment must be labeled, sized and placed appropriately for the needs of site.
- Prevent the discharge of soaps, solvents, detergents and other liquid wastes from construction sites.

PORTABLE TOILETS

- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless there is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet behind silt fence or place on a gravel pad and surround with sand bags.
- Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas.
- Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste hauler to remove leaking portable toilets and replace with properly operating unit.

EARTHEN STOCKPILE MANAGEMENT

- Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm drain inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other alternatives are reasonably available.
- Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of stockpile.
- Provide stable stone access point when feasible.
- Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage techniques that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.



- #### CONCRETE WASHOUTS
- Do not discharge concrete or cement slurry from the site.
 - Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste regulations and at an approved facility.
 - Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and associated materials on impervious barrier and within lot perimeter silt fence.
 - Install temporary concrete washouts per local requirements, where applicable. If an alternate method or product is to be used, contact your approval authority for review and approval. If local standard details are not available, use one of the two types of temporary concrete washouts provided on this detail.
 - Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.
 - Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.
 - Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
 - Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the washout itself to identify this location.
 - Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative or proprietary products, follow manufacturer's instructions.
 - At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

HERBICIDES, PESTICIDES AND RODENTICIDES




- Store and apply herbicides, pesticides and rodenticides in accordance with label restrictions.
- Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for use, ingredients and first aid steps in case of accidental poisoning.
- Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately.
- Do not stockpile these materials onsite.

HAZARDOUS AND TOXIC WASTE

- Create designated hazardous waste collection areas on-site.
- Place hazardous waste containers under cover or in secondary containment.
- Do not store hazardous chemicals, drums or bagged materials directly on the ground.

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING



EFFECTIVE: 04/01/19

| | | |
|---|----------------------------|----------------------|
| Project No: 543521 | REVISIONS/SUBMISSIONS 1 | Date 11-02-2021 |
| RESIDENTIAL SUBDIVISION HENDERSON COUNTY | 1 | HENDERSON COUNTY TRC |
| Revision Submission number within a triangle indicates changes made on this sheet | | |
|     PRELIMINARY - NOT FOR CONSTRUCTION | | |
| <p>Reviewed: WBE Drawn: AS-NOTED Checked: WBE Date: 2021-11-02 Phone: 1-828-232-4700 Fax: 1-828-232-1331 www.brooksea.com</p> | | |
| <p>RICH MOUNTAIN SUBDIVISION PHASE 1 RESIDENTIAL SUBDIVISION NORTH CAROLINA</p> | | |
| <p>C-5.10 Drawing Title: NCG01 DETAILS 1</p> | | |
| <p>File Location: L:\2021 Projects\543521\Rich Mt. Due Diligence\Drawings\Details\543521.dwg File Name: C-5.10.Dwg</p> | | |

| PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING | | | | | | | | | | | | | | | | | | | | | | | |
|---|--|--|---------|--|----------------------------------|---|-------|--|--|--|--|--|--|--|-----------------------|--|---|--|--|---|-----------------------------------|-----------------------------|--|
| SECTION A: SELF-INSPECTION | | | | | | | | | | | | | | | | | | | | | | | |
| <p>Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection Record.</p> <table border="1"> <thead> <tr> <th>Inspect</th> <th>Frequency (during normal business hours)</th> <th>Inspection records must include:</th> </tr> </thead> <tbody> <tr> <td>(1) Rain gauge maintained in good working order</td> <td>Daily</td> <td>Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those un(anc this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division.</td> </tr> <tr> <td>(2) E&SC Measures and within 24 hours of a rain event > 1.0 inch in 24 hours</td> <td>At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours</td> <td>1. Identification of the measures inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Indication of whether the measures were operating properly, 5. Description of maintenance needs for the measure, 6. Description, evidence, and date of corrective actions taken.</td> </tr> <tr> <td>(3) Stormwater discharge outfalls (SDCs)</td> <td>At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours</td> <td>1. Identification of the discharge outfalls inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 5. Indication of visible sediment leaving the site, 6. Description, evidence, and date of corrective actions taken.</td> </tr> <tr> <td>(4) Perimeter of site</td> <td>At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours</td> <td>If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future</td> </tr> <tr> <td>(5) Streams or wetlands onsite or offsite (where accessible)</td> <td>At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours</td> <td>If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit.</td> </tr> <tr> <td>(6) Ground stabilization measures</td> <td>After each phase of grading</td> <td>1. The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). 2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.</td> </tr> </tbody> </table> | | | Inspect | Frequency (during normal business hours) | Inspection records must include: | (1) Rain gauge maintained in good working order | Daily | Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those un(anc this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division. | (2) E&SC Measures and within 24 hours of a rain event > 1.0 inch in 24 hours | At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours | 1. Identification of the measures inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Indication of whether the measures were operating properly, 5. Description of maintenance needs for the measure, 6. Description, evidence, and date of corrective actions taken. | (3) Stormwater discharge outfalls (SDCs) | At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours | 1. Identification of the discharge outfalls inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 5. Indication of visible sediment leaving the site, 6. Description, evidence, and date of corrective actions taken. | (4) Perimeter of site | At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours | If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future | (5) Streams or wetlands onsite or offsite (where accessible) | At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours | If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit. | (6) Ground stabilization measures | After each phase of grading | 1. The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). 2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible. |
| Inspect | Frequency (during normal business hours) | Inspection records must include: | | | | | | | | | | | | | | | | | | | | | |
| (1) Rain gauge maintained in good working order | Daily | Daily rainfall amounts. If no daily rain gauge observations are made during weekend or holiday periods, and no individual-day rainfall information is available, record the cumulative rain measurement for those un(anc this will determine if a site inspection is needed). Days on which no rainfall occurred shall be recorded as "zero." The permittee may use another rain-monitoring device approved by the Division. | | | | | | | | | | | | | | | | | | | | | |
| (2) E&SC Measures and within 24 hours of a rain event > 1.0 inch in 24 hours | At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours | 1. Identification of the measures inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Indication of whether the measures were operating properly, 5. Description of maintenance needs for the measure, 6. Description, evidence, and date of corrective actions taken. | | | | | | | | | | | | | | | | | | | | | |
| (3) Stormwater discharge outfalls (SDCs) | At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours | 1. Identification of the discharge outfalls inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 5. Indication of visible sediment leaving the site, 6. Description, evidence, and date of corrective actions taken. | | | | | | | | | | | | | | | | | | | | | |
| (4) Perimeter of site | At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours | If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future | | | | | | | | | | | | | | | | | | | | | |
| (5) Streams or wetlands onsite or offsite (where accessible) | At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours | If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, and 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item (2)(a) of this permit. | | | | | | | | | | | | | | | | | | | | | |
| (6) Ground stabilization measures | After each phase of grading | 1. The phase of grading (installation of perimeter E&SC measures, clearing and grubbing, installation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). 2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible. | | | | | | | | | | | | | | | | | | | | | |
| NOTE: The rain inspection resets the required 7 calendar day inspection requirement. | | | | | | | | | | | | | | | | | | | | | | | |

| PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING | | | | | | | | | | | | | | |
|--|---|--|------------------|----------------------------|--|---|--|---|--|---|--|---|--|--|
| SECTION B: RECORDKEEPING | | | | | | | | | | | | | | |
| 1. E&SC Plan Documentation | | | | | | | | | | | | | | |
| <p>The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.</p> <table border="1"> <thead> <tr> <th>Item to Document</th> <th>Documentation Requirements</th> </tr> </thead> <tbody> <tr> <td>(a) Each E&SC measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation.</td> <td>Initial and date each E&SC measure on a copy of the approved E&SC plan or complete, date and sign an inspection report that lists each E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation.</td> </tr> <tr> <td>(b) A phase of grading has been completed. Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.</td> <td>Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase.</td> </tr> <tr> <td>(c) Ground cover is located and installed in accordance with the approved E&SC plan.</td> <td>Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.</td> </tr> <tr> <td>(d) The maintenance and repair requirements for all E&SC measures have been performed.</td> <td>Complete, date and sign an inspection report.</td> </tr> <tr> <td>(e) Corrective actions have been taken to E&SC measures. report to indicate the completion of the corrective action.</td> <td>Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the corrective action.</td> </tr> </tbody> </table> | | | Item to Document | Documentation Requirements | (a) Each E&SC measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation. | Initial and date each E&SC measure on a copy of the approved E&SC plan or complete, date and sign an inspection report that lists each E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation. | (b) A phase of grading has been completed. Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase. | Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase. | (c) Ground cover is located and installed in accordance with the approved E&SC plan. | Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications. | (d) The maintenance and repair requirements for all E&SC measures have been performed. | Complete, date and sign an inspection report. | (e) Corrective actions have been taken to E&SC measures. report to indicate the completion of the corrective action. | Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the corrective action. |
| Item to Document | Documentation Requirements | | | | | | | | | | | | | |
| (a) Each E&SC measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation. | Initial and date each E&SC measure on a copy of the approved E&SC plan or complete, date and sign an inspection report that lists each E&SC measure shown on the approved E&SC plan. This documentation is required upon the initial installation of the E&SC measures or if the E&SC measures are modified after initial installation. | | | | | | | | | | | | | |
| (b) A phase of grading has been completed. Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase. | Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate completion of the construction phase. | | | | | | | | | | | | | |
| (c) Ground cover is located and installed in accordance with the approved E&SC plan. | Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications. | | | | | | | | | | | | | |
| (d) The maintenance and repair requirements for all E&SC measures have been performed. | Complete, date and sign an inspection report. | | | | | | | | | | | | | |
| (e) Corrective actions have been taken to E&SC measures. report to indicate the completion of the corrective action. | Initial and date a copy of the approved E&SC plan or complete, date and sign an inspection report to indicate the completion of the corrective action. | | | | | | | | | | | | | |
| 2. Additional Documentation to be Kept on Site | | | | | | | | | | | | | | |
| <p>In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:</p> <ol style="list-style-type: none"> This General Permit as well as the Certificate of Coverage, after it is received. Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records. | | | | | | | | | | | | | | |
| 3. Documentation to be Retained for Three Years | | | | | | | | | | | | | | |
| <p>All data used to complete the e-NOI and all inspection records shall be maintained for a period of three years after project completion and made available upon request [40 CFR 122.41]</p> | | | | | | | | | | | | | | |

| PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING | | | | | | | | | | | | | | |
|--|--|--|------------|---|--|--|--|--|--|--|--|---|---|--|
| SECTION C: REPORTING | | | | | | | | | | | | | | |
| 1. Occurrences that Must be Reported | | | | | | | | | | | | | | |
| <p>Permittees shall report the following occurrences:</p> <ul style="list-style-type: none"> (a) Visible sediment deposition in a stream or wetland. (b) Oil spills if: <ul style="list-style-type: none"> • They are 25 gallons or more, • They are less than 25 gallons but cannot be cleaned up within 24 hours, • They cause sheen on surface waters (regardless of volume), or • They are within 100 feet of surface waters (regardless of volume). (c) Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref: 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref: 40 CFR 302.4) or G.S. 143-215.85. (d) Anticipated bypasses and unanticipated bypasses. (e) Noncompliance with the conditions of this permit that may endanger health or the environment. | | | | | | | | | | | | | | |
| 2. Reporting Timeframes and Other Requirements | | | | | | | | | | | | | | |
| <p>After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional office within the timeframes and in accordance with the other requirements listed below. Occurrences outside normal business hours may also be reported to the Department's Environmental Emergency Center personnel at (800) 858-0368.</p> | | | | | | | | | | | | | | |
| <table border="1"> <thead> <tr> <th>Occurrence</th> <th>Reporting Timeframes (After Discovery) and Other Requirements</th> </tr> </thead> <tbody> <tr> <td>(a) Visible sediment deposition in a stream or wetland</td> <td> <ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. • Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis. • If the stream is named on the NC 303(d) list as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired-waters conditions. </td> </tr> <tr> <td>(b) Oil spills and release of hazardous substances per Item 1(b)-(c) above</td> <td> <ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release. </td> </tr> <tr> <td>(c) Anticipated bypasses [40 CFR 122.41(m)(3)]</td> <td> <ul style="list-style-type: none"> • A report at least ten days before the date of the bypass, if possible. The report shall include an evaluation of the anticipated quality and effect of the bypass. </td> </tr> <tr> <td>(d) Unanticipated bypasses [40 CFR 122.41(m)(3)]</td> <td> <ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. • Within 7 calendar days, a report that includes an evaluation of the quality and effect of the bypass. </td> </tr> <tr> <td>(e) Noncompliance with the conditions of this permit that may endanger health or the environment[40 CFR 122.41(1)(6)]</td> <td> <ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. • Within 7 calendar days, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(1)(6)]. </td> </tr> </tbody> </table> | | | Occurrence | Reporting Timeframes (After Discovery) and Other Requirements | (a) Visible sediment deposition in a stream or wetland | <ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. • Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis. • If the stream is named on the NC 303(d) list as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired-waters conditions. | (b) Oil spills and release of hazardous substances per Item 1(b)-(c) above | <ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release. | (c) Anticipated bypasses [40 CFR 122.41(m)(3)] | <ul style="list-style-type: none"> • A report at least ten days before the date of the bypass, if possible. The report shall include an evaluation of the anticipated quality and effect of the bypass. | (d) Unanticipated bypasses [40 CFR 122.41(m)(3)] | <ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. • Within 7 calendar days, a report that includes an evaluation of the quality and effect of the bypass. | (e) Noncompliance with the conditions of this permit that may endanger health or the environment[40 CFR 122.41(1)(6)] | <ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. • Within 7 calendar days, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(1)(6)]. |
| Occurrence | Reporting Timeframes (After Discovery) and Other Requirements | | | | | | | | | | | | | |
| (a) Visible sediment deposition in a stream or wetland | <ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. • Within 7 calendar days, a report that contains a description of the sediment and actions taken to address the cause of the deposition. Division staff may waive the requirement for a written report on a case-by-case basis. • If the stream is named on the NC 303(d) list as impaired for sediment-related causes, the permittee may be required to perform additional monitoring, inspections or apply more stringent practices if staff determine that additional requirements are needed to assure compliance with the federal or state impaired-waters conditions. | | | | | | | | | | | | | |
| (b) Oil spills and release of hazardous substances per Item 1(b)-(c) above | <ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. The notification shall include information about the date, time, nature, volume and location of the spill or release. | | | | | | | | | | | | | |
| (c) Anticipated bypasses [40 CFR 122.41(m)(3)] | <ul style="list-style-type: none"> • A report at least ten days before the date of the bypass, if possible. The report shall include an evaluation of the anticipated quality and effect of the bypass. | | | | | | | | | | | | | |
| (d) Unanticipated bypasses [40 CFR 122.41(m)(3)] | <ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. • Within 7 calendar days, a report that includes an evaluation of the quality and effect of the bypass. | | | | | | | | | | | | | |
| (e) Noncompliance with the conditions of this permit that may endanger health or the environment[40 CFR 122.41(1)(6)] | <ul style="list-style-type: none"> • Within 24 hours, an oral or electronic notification. • Within 7 calendar days, a report that contains a description of the noncompliance, and its causes; the period of noncompliance, including exact dates and times, and if the noncompliance has not been corrected, the anticipated time noncompliance is expected to continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(1)(6)]. | | | | | | | | | | | | | |

| RICH MOUNTAIN SUBDIVISION PHASE 1 | | RESIDENTIAL SUBDIVISION | | NORTH CAROLINA | |
|---|------------|-------------------------|------------------|-----------------------|----------------------|
| Project No: | C-543521 | HENDERSON COUNTY | HENDERSON COUNTY | NORTH CAROLINA | NORTH CAROLINA |
| Drawing Title: | C-5.11 | | | | |
| File Location: L:\2021 Projects\5-3521_Rainfall_Falls_Rain Min Due Diligence\Drawings\Details\4342.dwg | | | | | |
| Date: | 11-02-2021 | No.: | 1 | REVISIONS/SUBMISSIONS | HENDERSON COUNTY TRC |
| Revision Submission number within a triangle indicates changes made on this sheet | | | | | |
|   | | | | | |
| PRELIMINARY - NOT FOR CONSTRUCTION | | | | | |
| Reviewed: | WBE | Scale: | AS-NOTED | Checked: | WBE |
| Designed: | WBE | Drawn: | WBE | Date: | 2021-11-02 |
| 15 Arlington Street Asheville, NC 28801 Phone: 1-828-232-4700 Fax: 1-828-232-1331 www.brooksea.com | | | | | |